

---

**CliMetLab**

***Release 0.19.2***

**ECMWF**

**Jan 09, 2024**



## **CONTENTS**

<b>1 Documentation</b>	<b>3</b>
<b>2 License</b>	<b>195</b>



**Warning:** This documentation is work in progress. It is not yet ready.

*CliMetLab* is a Python package aiming at simplifying access to climate and meteorological datasets, allowing users to focus on science instead of technical issues such as data access and data formats. It is mostly intended to be used in [Jupyter](#) notebooks, and be interoperable with all popular data analytic packages, such as [NumPy](#), [Pandas](#), [Xarray](#), [SciPy](#), [Matplotlib](#), etc. as well as machine learning frameworks, such as [TensorFlow](#), [Keras](#) or [PyTorch](#). See [Overview](#) for more information.



## DOCUMENTATION

- *Overview*
- *Installing*
- *First Steps Tutorial*
- *Examples*

### 1.1 Overview

*CliMetLab* is a Python package which is intended to be used in [Jupyter](#) notebooks. Its main goal is to greatly reduce boilerplate code by providing high-level unified access to meteorological and climate datasets, allowing scientists to focus on their research instead of solving technical issues. Datasets are automatically downloaded, cached and transform into standard Python data structures such as [NumPy](#), [Pandas](#) or [Xarray](#), that can then be fed into scientific packages like [SciPy](#) and [TensorFlow](#). *CliMetLab* also aims at simplifying plotting of 2D maps, by automatically selecting the most appropriate styles and projections for any given data.

The goal of *CliMetLab* is to simplify access to climate and meteorological datasets, by hiding the access methods and data formats. The snippet of code below would download the dataset *dataset-name*, cache it locally and decodes its content as a NumPy array:

```
import climetlab as clm

data = clm.load_dataset("dataset-name")
a = data.to_numpy()
```

To achieve this, *CliMetLab* introduces two concepts: *Data source* and *Dataset*. Data sources represent various access methods, such as reading files, downloading from a web site or using APIs.

*CliMetLab* provides the interface between the left side and the right side of the figure below:

*CliMetLab* also provides very high-level map plotting facilities. By default *CliMetLab* will automatically select the most appropriate way to plot a dataset, choosing the best projection, colours and other graphical attributes. Users can then control how maps are drawn by overriding the automatic choices with their own.

```
import climetlab as clm

data = clm.load_dataset("some-dataset")
clm.plot_map(data)
```

## 1.2 Installing

### 1.2.1 Pip install

To install CliMetLab, just run the following command:

```
pip install climetlab
```

The CliMetLab pip package has been tested successfully with the latest versions of its dependencies ([build logs](#)).

### 1.2.2 Conda install

No conda package has been created yet. `pip install climetlab` can be used in a conda environment.

---

**Note:** Mixing pip and conda could create some dependencies issues, we recommend installing as many dependencies as possible with conda, then install CliMetLab with pip, [as recommended by the anaconda team](#).

---

### 1.2.3 Troubleshooting

#### Python 3.8 or above is required

CliMetLab requires Python 3.8 or above (mainly due the dependency *numpy*). Depending on your installation, you may need to substitute pip to pip3 in the examples below. See the [build logs](#) to know on which version of Python CliMetLab is automatically tested.

#### No matching distribution found for ...

If the installation fails with the following error:

```
Collecting ecmwflibs>=x.x.x (from climetlab)
  Could not find a version that satisfies the requirement ecmwflibs>=0.0.90 (from
  -> climetlab) (from versions: )
No matching distribution found for ecmwflibs>=x.x.x (from climetlab)
```

you will need to make sure that you are using the latest version of pip (>=21.0.0):

```
% pip install --upgrade pip
% pip install climetlab
```

**WARNING: Retrying (Retry(total=4, connect=None, ...**

If you are installing CliMetLab (or any other package) without internet access. You can get a similar error. This happens for instance on Kaggle when you are not logged in or when your account has not been verified.

```
WARNING: Retrying (Retry(total=4, connect=None, read=None, redirect=None, status=None))
after connection broken by 'NewConnectionError(': Failed to establish a new connection:
[Errno -3] Temporary failure in name resolution')':....
```

**Module enum has no attribute 'IntFlag'**

If the installation fails with the following error:

```
AttributeError: module 'enum' has no attribute 'IntFlag'
```

This means that there is an old version of the `enum` package on your system that needs to be removed:

```
% pip uninstall -y enum34
% pip install climetlab
```

## 1.3 First Steps Tutorial

This is an easy to follow tutorial that gets you up to speed with *CliMetLab* to access scientific climate data. It assumes you have basic Python programming knowledge.

So, let's start with what *CliMetLab* does best:

### 1.3.1 Getting data

*CliMetLab* provides two main ways to access climate and meteorological data

1. Data Sources ([details](#))
2. Datasets ([details](#))

#### Data Sources

In *CliMetLab*, a *Data Source* refers to a local or remote storage server or data archive from where we can download or access files related to climate data.

To get started, let us first import *CliMetLab* at the top of our Python notebook:

```
import climetlab as cml
```

Now download `test.grib` (example GRIB file) to your project directory, or if you have `wget` command available, run following in your notebook:

```
!wget https://raw.githubusercontent.com/ecmwf/climetlab/main/docs/examples/test.grib
```

GRIB is a file format for storage and sharing of gridded meteorological data. You can think of gridded data as weather or some other data that is associated with specific locations using coordinates. For example, wind speed data for every longitude and latitude on a two dimensional grid.

The GRIB format (version 1 and 2) is endorsed by WMO. GRIB (GRIdded Binary) is a binary file format so you cannot look at it using a text editor. But you sure can use *CliMetLab* to explore it:

```
grib_data = cml.load_source("file", "test.grib")
```

Here we used `load_source` method from *CliMetLab* to load our GRIB file into `grib_data` variable. The first argument "file" specifies the type of our data source. Which currently is indeed a local file that we downloaded. The second argument is the path to that file.

Let's plot this data using the `plot_map` convenience method:

```
cml.plot_map(grib_data, title=True, path="test-grib-plot.svg")
```

The `title` and `path` arguments supplied to `plot_map` are optional. When `title` is set to `True`, the plot will include the title of the data from our data file. If you specify the `path` ending with a supported format (`.svg`, `.png`, `.pdf`), the plot will be saved at the specified location.

You can also use `load_source` to directly download and load files from remote server, in one step. For example, let's download and plot a NetCDF file:

```
netcdf_url = "https://raw.githubusercontent.com/ecmwf/climetlab/main/docs/examples/test.nc"
netcdf_data = cml.load_source("url", netcdf_url)
cml.plot_map(netcdf_data)
```

If you don't know already, NetCDF is another commonly used data format for transporting scientific data.

So, we have downloaded and plotted scientific weather data, can we convert this data to work with our favorite Data Science library? Pandas, Xarray or Numpy? Don't worry, *CliMetLab* has got you covered.

If your data is gridded data, like in our examples above, you can simply call `to_xarray()` method to convert it to an `Xarray` object:

```
grib_xr = grib_data.to_xarray()
# as well as:
netcdf_xr = netcdf_data.to_xarray()
```

*CliMetLab* will infer the type of data by probing the downloaded file. If the file contains gridded data, such as meteorological fields, they will be accessible as an `Xarray` dataset, using the `to_xarray()` method. If the file contains point data, such as observations, they can be converted to a Pandas data frame via the `to_pandas()` method. Other data may only be available as NumPy arrays using the `to_numpy()` method.

Observations are usually data points corresponding to time for a certain location unlike gridded data that contains data points that is usually for a range of locations. For example, monthly average temperature of Lahore for the past ten years.

The following example downloads a `.csv` file from NOAA's *International Best Track Archive for Climate Stewardship (IBTrACS)* using the `url` data source. The file is downloaded into the local cache. We then convert it to a Pandas frame. The rows corresponding to the severe tropical cyclone `Uma` are extracted and plotted.

```
import climetlab as cml

data = cml.load_source(
    "url",
    (
        "https://www.ncei.noaa.gov/data/international-best-track-archive-for-climate-
        stewardship-ibtracs"
```

(continues on next page)

(continued from previous page)

```

    "/v04r00/access/csv/ibtracs.SP.list.v04r00.csv"
),
)

pd = data.to_pandas()
uma = pd[pd.NAME == "UMA:VELI"]
cml.plot_map(uma, style="cyclone-track")

```

The Data Sources implement various methods to access and decode data. When data are downloaded from a remote site, they are *cached* on the local computer.

The first argument to `load_source` can take the following values:

Argument value	Description
"file"	A path to a local file name. <a href="#">Read more</a>
"url"	A URL to a remote file. <a href="#">Read more</a>
"cds"	A request to retrieve data from the <a href="#">Copernicus Climate Data Store</a> (CDS). Requires an account. <a href="#">Read more</a>
"mars"	A request to retrieve data from ECMWF's meteorological archive (MARS), using the <a href="#">ECMWF web API</a> . Requires an account. <a href="#">Read more</a>

To read more about Data Sources, head over to [Data Sources guide](#).

Now let's dive into the second way that you can access climate scientific data using *CliMetLab*:

## Datasets

Datasets are a higher-level concept compared to data sources.

---

**Todo:** metadata, hidden access to sources, control plotting, control conversion to pandas

---

The following Python code:

```

import climetlab as cml

data = cml.load_dataset("hurricane-database", basin="atlantic")
print(data.home_page)

```

will print:

```
https://www.aoml.noaa.gov/hrd/hurdat/Data_Storm.html
```

then,

```

irma = data.to_pandas(name="irma", year=2017)
cml.plot_map(irma)

```

will plot:

Compare that with the [data source example](#).

### 1.3.2 Simple plotting

*CliMetLab* will try to select the best way to plot data.

```
cml.plot_map(data)
```

Below are the parameters you can pass to the plot function:

Name	Value	Default	Description
title	str or bool	False	The title of the plot. Use True for automatic.
projection	str	None	The name of a map projection. Use None for automatic. See below for possible values.
style	str	None	The name of a plotting to apply. Use None for default. See below for possible values.
foreground	str	None	TODO. See below for possible values.
background	str	None	TODO. See below for possible values.
path	str	None	Save the plot in a file instead of displaying it. The file type is inferred from the path extension (.png, .pdf, .svg, ...)

You can find out what are the possible values for *projection*, *style*, *foreground* and *background* parameters using the code below:

```
import climetlab.plotting

# List of possible projections
for p in climetlab.plotting.projections():
    print(p)

# List of possible styles
for p in climetlab.plotting.styles():
    print(p)

# List of possible backgrounds/foregrounds
for p in climetlab.plotting.layers():
    print(p)
```

To get more information about a given projection, in a Jupyter Notebook:

```
from climetlab.plotting import projection

projection("global")
```

will output:

Name:	global
Collection:	projections
Path:	/opt/venv/lib/python3.7/site-packages/climetlab/data/projections/global.yaml
Definition:	<pre>magics:   mmap:     subpage_lower_left_latitude: -90.0     subpage_lower_left_longitude: -180.0     subpage_map_projection: cylindrical     subpage_upper_right_latitude: 90.0     subpage_upper_right_longitude: 180.0</pre>

### 1.3.3 Advanced plotting

**Todo:** Improve documentation.

There are two options to plot several datasets on the same map. If you do not need to specify data specific parameters (e.g. *style*), you can call `cml.plot_map()` with a list of data objects.

```
cml.plot_map((data1, data2), foreground=False)
```

or, if you want to specify a per-data custom *style*, you can use `cml.new_map()`:

```
p = cml.new_plot(projection="global")
p.plot_map(data1, style="style1")
p.plot_map(data2, style="style2")
p.show()
```

## 1.4 Examples

Here is a list of example notebooks to illustrate how to access data, create plots, and do machine learning using CliMetLab.

You can run this notebook in , in , in

```
[1]: !pip3 install --quiet climetlab
```

```
[2]: !test -f test.grib || wget https://github.com/ecmwf/climetlab/raw/main/docs/examples/
→test.grib
```


```
[3]: !test -f test.nc || wget https://github.com/ecmwf/climetlab/raw/main/docs/examples/test.
→nc
```


### 1.4.1 Reading data from a file

```
[4]: import climetlab as cml
```

#### Plot GRIB data


```
[5]: source = cml.load_source("file", "test.grib")
for s in source:
    cml.plot_map(s)
```






#### Plot NetCDF data

```
[6]: source = cml.load_source("file", "test.nc")
for s in source:
    cml.plot_map(s)
```





You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab
```

#### 1.4.2 Downloading from an URL

```
[2]: import climetlab as cml
```


```
[3]: URL = "https://www.ncei.noaa.gov/data/international-best-track-archive-for-climate-  
stewardship-ibtracs/v04r00/access/csv/ibtracs.SP.list.v04r00.csv"
```

```
[4]: data = cml.load_source("url", URL)
```

```
[5]: pd = data.to_pandas()  
  
/usr/local/lib/python3.9/site-packages/IPython/core/interactiveshell.py:3418:  
DtypeWarning: Columns (1,2,8,9,14,25,161,162) have mixed types. Specify dtype option on  
import or set low_memory=False.  
exec(code_obj, self.user_global_ns, self.user_ns)
```

```
[6]: uma = pd[pd.NAME == "UMA:VELI"]
```

```
[7]: cml.plot_map(uma, style="cyclone-track")
```




You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab
```


### 1.4.3 Retrieve ERA5 data from the CDS

```
[2]: import climetlab as cml
```

```
[6]: source = cml.load_source(
    "cds",
    "reanalysis-era5-single-levels",
    variable=["2t", "msl"],
    product_type="reanalysis",
    area=[50, -50, 20, 50],
    date="2012-12-12",
    time="12:00",
)
for s in source:
    cml.plot_map(s)
```



```
[8]: source = cml.load_source(  
    "cds",  
    "reanalysis-era5-single-levels",  
    variable=["2t", "msl"],  
    product_type="reanalysis",  
    area=[50, -50, 20, 50],  
    date="2012-12-12",  
    time="12:00",  
    format="netcdf",  
)  
for s in source:  
    cml.plot_map(s)
```






```
[10]: source.to_xarray()
```

```
[10]: <xarray.Dataset>
Dimensions:    (latitude: 121, longitude: 401, time: 1)
Coordinates:
  * longitude  (longitude) float32 -50.0 -49.75 -49.5 -49.25 ... 49.5 49.75 50.0
  * latitude   (latitude) float32 50.0 49.75 49.5 49.25 ... 20.5 20.25 20.0
  * time       (time) datetime64[ns] 2012-12-12T12:00:00
Data variables:
  t2m        (time, latitude, longitude) float32 ...
  msl        (time, latitude, longitude) float32 ...
Attributes:
  Conventions: CF-1.6
  history:    2021-03-22 10:05:13 GMT by grib_to_ncdf-2.16.0: /opt/ecmw...
```

```
[12]: cml.plot_map(source.to_xarray(), title=True)
```




You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab
```

#### 1.4.4 Retrieve data ECMWF MARS archive

```
[2]: import climetlab as cml
```

```
[3]: source = cml.load_source(
    "mars",
    param=["2t", "msl"],
    levtype="sfc",
    area=[50, -50, 20, 50],
    grid=[1, 1],
    date="2012-12-13",
)
for s in source:
    cml.plot_map(s)
```



```
[4]: source.to_xarray()
```

```
[4]: <xarray.Dataset>
```

Dimensions: (latitude: 31, longitude: 101)

Coordinates:

number	int64 ...
time	datetime64[ns] ...
step	timedelta64[ns] ...
surface	int64 ...
* latitude	(latitude) float64 50.0 49.0 48.0 47.0 ... 23.0 22.0 21.0 20.0
* longitude	(longitude) float64 -50.0 -49.0 -48.0 -47.0 ... 48.0 49.0 50.0
valid_time	datetime64[ns] ...

Data variables:

(continues on next page)

(continued from previous page)

```
t2m      (latitude, longitude) float32 ...
msl      (latitude, longitude) float32 ...
Attributes:
GRIB_edition:          1
GRIB_centre:           ecmf
GRIB_centreDescription: European Centre for Medium-Range Weather Forecasts
GRIB_subCentre:         0
Conventions:            CF-1.7
institution:           European Centre for Medium-Range Weather Forecasts
history:               2021-03-24T13:23:13 GRIB to CDM+CF via cfgrib-0...
```

You can run this notebook in , in , in


```
[20]: !pip install --quiet climetlab
```

#### 1.4.5 Access ECMWF Open Data feed


```
[21]: import climetlab as cml
```

```
[22]: source = cml.load_source(
    "ecmwf-open-data",
    param=["2t", "msl"],
)
for s in source:
    cml.plot_map(s, title=True)
```

Sunday 06 February 2022 00 UTC ecmf t+0 VT:Sunday 06 February 2022 00 UTC 2 m 2 metre temperature



```
Sunday 06 February 2022 00 UTC ecmf t+0 VT:Sunday 06 February 2022 00 UTC meanSea Mean sea level pressure
```



```
[23]: source.to_xarray()
```

```
<xarray.Dataset>
Dimensions:          (latitude: 451, longitude: 900)
Coordinates:
  time            datetime64[ns] ...
  step             timedelta64[ns] ...
  heightAboveGround float64 ...
* latitude        float64 90.0 89.6 89.2 ... -89.2 -89.6 -90.0
* longitude       float64 -180.0 -179.6 -179.2 ... 179.2 179.6
  valid_time      datetime64[ns] ...
  meanSea         float64 ...
Data variables:
  t2m              (latitude, longitude) float32 ...
  msl              (latitude, longitude) float32 ...
Attributes:
  GRIB_edition:    2
  GRIB_centre:     ecmf
  GRIB_centreDescription: European Centre for Medium-Range Weather Forecasts
  GRIB_subCentre:   0
  Conventions:      CF-1.7
  institution:     European Centre for Medium-Range Weather Forecasts
  history:         2022-02-06T12:42 GRIB to CDM+CF via cfrgrib-0.9.1...
```

You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab matplotlib
```

## 1.4.6 ERA5-based datasets

```
[2]: import numpy as np  
import matplotlib.pyplot as plt
```

```
[3]: import climetlab as cml
```

```
[4]: cml.plotting_options(width=400)
```


### Surface temperature in France

```
[5]: ds = cml.load_dataset("era5-temperature", period=(1979, 1982), domain="France", time=12)
```

```
[6]: %time  
len(ds)  
  
CPU times: user 558 ms, sys: 94.9 ms, total: 653 ms  
Wall time: 686 ms
```

```
[6]: 1461
```

```
[7]: cml.plot_map(ds[-1])
```



```
[8]: %time  
ds.to_numpy().shape
```

```
CPU times: user 603 ms, sys: 124 ms, total: 727 ms
Wall time: 739 ms
```


```
[8]: (1461, 63, 63)
```

```
[9]: average = np.mean(ds.to_numpy(), axis=0)
```

```
[10]: average
```

```
[10]: array([[283.75848794, 283.5668571 , 283.28540925, ..., 283.07590083,
   283.10228607, 283.10129547],
 [283.4987798 , 283.60046529, 283.65712864, ..., 283.17566394,
 283.24349259, 283.31315138],
 [283.27489098, 282.96305539, 283.02593639, ..., 283.29626172,
 283.42080452, 283.51664 ],
 ...,
 [291.8236389 , 291.01727633, 290.47778203, ..., 292.8580171 ,
 292.87150182, 293.54986986],
 [292.33919705, 292.04851029, 291.94756675, ..., 292.50002974,
 292.48287807, 294.12919668],
 [292.80611291, 292.51362676, 292.36608895, ..., 292.37801758,
 292.20149706, 292.06164609]])
```

```
[11]: cml.plot_map(average, metadata=ds[0])
```



```
[12]: x = ds.to_xarray()
```

```
[13]: x
```

```
[13]: <xarray.Dataset>
Dimensions:      (latitude: 63, longitude: 63, time: 1461)
Coordinates:
  * time        (time) datetime64[ns] 1979-01-01T12:00:00 ... 1982-12-31T12:0...
    number      int64 0
    step        timedelta64[ns] 00:00:00
    surface     int64 0
  * latitude    (latitude) float64 54.5 54.25 54.0 53.75 ... 39.5 39.25 39.0
  * longitude   (longitude) float64 -6.0 -5.75 -5.5 -5.25 ... 8.75 9.0 9.25 9.5
    valid_time  (time) datetime64[ns] 1979-01-01T12:00:00 ... 1982-12-31T12:0...
Data variables:
  t2m         (time, latitude, longitude) float32 269.13837 ... 285.14648
```


```
[14]: point = x.t2m.isel(latitude=50, longitude=5) - 273.15
```

```
[15]: point.plot()
```


```
[15]: [<matplotlib.lines.Line2D at 0x10f788130>]
```

```
[16]: x.t2m.plot()
```

```
[16]: (array([6.200000e+01, 1.715000e+03, 2.437000e+04, 2.066870e+05,
       1.035682e+06, 2.078559e+06, 1.673685e+06, 6.841460e+05,
       9.120900e+04, 2.594000e+03]),
 array([247.29189, 254.00276, 260.71362, 267.4245 , 274.13538, 280.84625,
       287.55713, 294.268 , 300.97888, 307.68976, 314.40063],
       dtype=float32),
 <BarContainer object of 10 artists>)
```




[17]: `cml.plot_map(x)`



## Precipitations from Ireland

```
[18]: ds = cml.load_dataset(  
    "era5-precipitations", period=(1979, 1982), domain="Ireland", time=12  
)
```

```
[19]: cml.plot_map(ds[0])
```



You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab tensorflow
```



### 1.4.7 Machine learning example


```
[2]: from tensorflow.keras.layers import Input, Dense, Flatten  
from tensorflow.keras.models import Sequential
```


```
[3]: import climetlab as cml
```


Load the high-low data set and plot all the fields and their label


```
[4]: highlow = cml.load_dataset("high-low")
for field, label in highlow.fields():
    cml.plot_map(field, width=256, title=highlow.title(label))
```



































### Get the train and test sets

```
[5]: (x_train, y_train, f_train), (x_test, y_test, f_test) = highlow.load_data(  
    test_size=0.3, fields=True  
)
```

## Build the model

```
[6]: model = Sequential()
model.add(Input(shape=x_train[0].shape))
model.add(Flatten())
model.add(Dense(64, activation="sigmoid"))
model.add(Dense(4, activation="softmax"))
```

```
[7]: model.compile(optimizer="adam", loss="categorical_crossentropy", metrics=["accuracy"])
print(model.summary())
```

Model: "sequential"

Layer (type)	Output Shape	Param #
flatten (Flatten)	(None, 441)	0
dense (Dense)	(None, 64)	28288
dense_1 (Dense)	(None, 4)	260
<hr/>		
Total params: 28,548		
Trainable params: 28,548		
Non-trainable params: 0		
<hr/>		
None		

## Train the model

```
[8]: h = model.fit(x_train, y_train, epochs=100, verbose=0)
```


Evaluate the model on the test set


```
[9]: model.evaluate(x_test, y_test)
1/1 [=====] - 0s 1ms/step - loss: 0.2691 - accuracy: 0.9167
[0.26906612515449524, 0.9166666865348816]
```


## Plot the predictions


```
[10]: predicted = model.predict(x_test)

for p, f in zip(predicted, f_test):
    cml.plot_map(f, width=256, title=highlow.title(p))
```









You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab
```

## 1.4.8 BUFR data

```
[2]: import climetlab as cml
```

```
[3]: source = cml.load_dataset("sample-bufr-data")
```

```
[4]: source
```

```
[4]: YAML[/Users/baudouin/git/climetlab/climetlab/datasets/sample-bufr-data.yaml]
```

See <https://github.com/ecmwf/pdbufr>

```
[5]: pd = source.to_pandas(  
    columns=[  
        "stationNumber",  
        "latitude",  
        "longitude",  
        "data_datetime",  
        "pressure",  
        "airTemperature",  
    ],  
    filters={},  
)
```

```
[6]: pd.head()
```

```
[6]:   stationNumber  latitude  longitude  pressure  airTemperature \\\n0          907      58.47     -78.08  100300.0       258.3  
1          907      58.47     -78.08  100000.0       259.7  
2          907      58.47     -78.08   99800.0       261.1  
3          907      58.47     -78.08   99100.0       261.7  
4          907      58.47     -78.08   92500.0       258.1  
  
      data_datetime  
0  2008-12-08 12:00:00  
1  2008-12-08 12:00:00  
2  2008-12-08 12:00:00  
3  2008-12-08 12:00:00  
4  2008-12-08 12:00:00
```

```
[7]: pd.tail()
```


```
[7]:   stationNumber  latitude  longitude  pressure  airTemperature \\\n26191          968      25.03     121.52  10000.0       197.9  
26192          968      25.03     121.52   9520.0       196.3  
26193          968      25.03     121.52   7000.0       201.5  
26194          968      25.03     121.52   5000.0       209.1  
26195          968      25.03     121.52   3000.0       217.3
```

(continues on next page)

(continued from previous page)

```
data_datetime  
26191 2008-12-08 12:00:00  
26192 2008-12-08 12:00:00  
26193 2008-12-08 12:00:00  
26194 2008-12-08 12:00:00  
26195 2008-12-08 12:00:00
```

```
[8]: cml.plot_map(pd, projection="global")
```



You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab[interactive]
```

#### 1.4.9 ECMWF Observation bespoke format (ODB)

```
[2]: import climetlab as cml
```

```
[3]: source = cml.load_source(  
    "mars",  
    type="ofb",  
    obsgroup="conv",  
    time="12",  
    format="odb",  
    reportype=16001,  
    date="2020-05-18",  
)
```

```
[4]: pd = source.to_pandas()
```

[5]:	pd							
[5]:								
0	type	expver	class	stream	andate	antime	reportype	\
1	263	0001	1	1025	20200518	120000	16001	
2	263	0001	1	1025	20200518	120000	16001	
3	263	0001	1	1025	20200518	120000	16001	
4	263	0001	1	1025	20200518	120000	16001	
...	...	...	...	...	...	...	...	...
410015	263	0001	1	1025	20200518	120000	16001	
410016	263	0001	1	1025	20200518	120000	16001	
410017	263	0001	1	1025	20200518	120000	16001	
410018	263	0001	1	1025	20200518	120000	16001	
410019	263	0001	1	1025	20200518	120000	16001	
	numtsl@desc	timeslot@timeslot_index		seqno@hdr	...	...	\	
0		17		15	4443	...		
1		17		15	4443	...		
2		17		15	4443	...		
3		17		15	4443	...		
4		17		15	4443	...		
...	...	...	...	...	...	...	...	
410015		17		15	9133718	...		
410016		17		15	9133718	...		
410017		17		15	9133718	...		
410018		17		15	9133718	...		
410019		17		15	9133718	...		
	datum_rdbflag@body	biascorr@body	biascorr_fg@body	qc_pge@body	...		\	
0		0	NaN	NaN	NaN			
1		0	NaN	NaN	NaN			
2		0	0.0	0.0	0.0			
3		0	0.0	0.0	0.0			
4		0	0.0	0.0	0.0			
...	...	...	...	...	...	...	...	
410015		0	0.0	0.0	0.0			
410016		0	0.0	0.0	0.0			
410017		0	0.0	0.0	0.0			
410018		0	0.0	0.0	0.0			
410019		0	0.0	0.0	0.0			
	an_depar@body	fg_depar@body	obs_error@errstat	...			\	
0	-10.560810	-14.283884	41.155659					
1	36.250599	34.712360	41.155659					
2	-9.160848	-12.384340	33.596455					
3	NaN	NaN	NaN					
4	2.482570	2.683633	1.408449					
...	...	...	...	...	...	...	...	
410015	NaN	NaN	NaN					
410016	NaN	NaN	NaN					
410017	NaN	NaN	NaN					
410018	NaN	NaN	NaN					
410019	NaN	NaN	NaN					

(continues on next page)

(continued from previous page)


```

final_obs_error@errstat  fg_error@errstat  eda_spread@errstat
0                      41.155659      25.144444      13.044278
1                      41.155659      25.144444      13.044278
2                     33.596455      0.260278      0.011694
3                         NaN          NaN          NaN
4                     1.408449      0.502528      0.395115
...
410015                  ...          ...          ...
410016                  NaN          NaN          NaN
410017                  NaN          NaN          NaN
410018                  NaN          NaN          NaN
410019                  NaN          NaN          NaN

[410020 rows x 51 columns]

```

[6]: `cml.plot_map(pd)`



You can run this notebook in , in , in

[1]: `# !pip install --quiet climetlab`

### 1.4.10 Meteonet

This is an retrieve an plot various data types from <https://github.com/meteofrance/meteonet>

[2]: `import climetlab as cml`

## Radar images

```
[3]: ds = cml.load_dataset("meteonet-samples-radar")
```

```
[4]: ds
```


```
[4]: <climetlab.datasets.meteonet_samples.radar.MeteonetRadar at 0x104319b50>
```

```
[5]: ds.licence
```

```
[5]: 'https://meteonet.umr-cnrm.fr/dataset/LICENCE.md'
```

```
[6]: cml.plot_map(ds)
```

/Users/baudouin/git/climetlab/climetlab/normalize.py:17: UserWarning: Deprecated  
 →decorator @normalize\_arg. Use @normalise on each argument instead.  
 warnings.warn(



```
[7]: ds.to_xarray()
```

```
[7]: <xarray.Dataset>
```

Dimensions: (time: 45, y: 565, x: 784)

Coordinates:

* x	(x)	int64	0 1 2 3 4 5 6 7 8 ... 776 777 778 779 780 781 782 783
* y	(y)	int64	0 1 2 3 4 5 6 7 8 ... 557 558 559 560 561 562 563 564

(continues on next page)

(continued from previous page)

```

lon      (y, x) float64 -5.832 -5.822 -5.812 -5.802 ... 1.978 1.988 1.998
lat      (y, x) float64 51.89 51.89 51.89 51.89 ... 46.25 46.25 46.25 46.25
* time    (time) datetime64[ns] 2016-08-21T00:10:00 ... 2016-08-31T00:30:00
Data variables:
rainfall (time, y, x) int16 -1 -1 -1 -1 -1 -1 -1 -1 ... 0 0 0 0 0 0 0 0

```

## Ground station observations


[8]: `ds = cml.load_dataset("meteonet-samples-ground-stations", domain="SE")`

[9]: `ds.to_pandas()`

	number_sta	lat	lon	height_stn	date	dd	\
0	1027003	45.83000	5.11000	196.0	2016-01-01 00:00:00	Nan	
1	1033002	46.09000	5.81000	350.0	2016-01-01 00:00:00	0.0	
2	1034004	45.77000	5.69000	330.0	2016-01-01 00:00:00	0.0	
3	1072001	46.20000	5.29000	260.0	2016-01-01 00:00:00	Nan	
4	1089001	45.98000	5.33000	252.0	2016-01-01 00:00:00	0.0	
...	...	...	...	...	...	...	...
111618	84085004	43.94000	5.23000	488.0	2016-01-01 23:54:00	100.0	
111619	84086001	43.81000	5.15000	672.0	2016-01-01 23:54:00	140.0	
111620	84087001	44.14000	4.86000	55.0	2016-01-01 23:54:00	130.0	
111621	84107002	44.04067	5.49283	836.0	2016-01-01 23:54:00	120.0	
111622	84150001	44.34000	4.91000	141.0	2016-01-01 23:54:00	110.0	
	ff	precip	hu	td	t	psl	
0	NaN	NaN	98.0	278.75	279.05	NaN	
1	0.0	0.0	99.0	278.25	278.35	NaN	
2	0.0	0.0	100.0	279.15	279.15	NaN	
3	NaN	0.0	NaN	NaN	276.55	NaN	
4	0.0	0.0	95.0	278.85	279.55	102720.0	
...	...	...	...	...	...	...	...
111618	2.0	0.0	94.0	280.05	280.95	NaN	
111619	7.6	0.0	93.0	279.65	280.75	NaN	
111620	5.0	0.0	76.0	281.25	285.35	101760.0	
111621	3.8	0.2	99.0	278.55	278.65	NaN	
111622	3.1	0.0	82.0	281.85	284.85	NaN	

[111623 rows x 12 columns]

[10]: `cml.plot_map(ds)`



## Weather models

```
[11]: ds = cml.load_dataset("meteonet-samples-weather-models", model="arome")
```

```
[12]: ds.to_xarray()
```

```
[12]: <xarray.Dataset>
Dimensions:           (time: 1, step: 25, heightAboveGround: 1, latitude: 227, longitude: 315)
Coordinates:
  * time            (time) datetime64[ns] 2018-05-01
  * step             (step) timedelta64[ns] 00:00:00 ... 1 days 00:00:00
  * heightAboveGround (heightAboveGround) int64 2
  * latitude         (latitude) float64 51.9 51.87 51.85 ... 46.3 46.27 46.25
  * longitude        (longitude) float64 -5.842 -5.817 -5.792 ... 1.983 2.008
  * valid_time       (time, step) datetime64[ns] dask.array<chunksize=(1, 25), meta=np._ndarray>
Data variables:
  t2m                (time, step, heightAboveGround, latitude, longitude) float32 dask.array<chunksize=(1, 25, 1, 227, 315), meta=np._ndarray>
  d2m                (time, step, heightAboveGround, latitude, longitude) float32 dask.array<chunksize=(1, 25, 1, 227, 315), meta=np._ndarray>
  r                  (time, step, heightAboveGround, latitude, longitude) float32 dask.array<chunksize=(1, 25, 1, 227, 315), meta=np._ndarray>
Attributes:
```


(continues on next page)

(continued from previous page)

```
GRIB_edition:      1
GRIB_centre:       lfpw
GRIB_centreDescription: French Weather Service - Toulouse
GRIB_subCentre:    0
Conventions:       CF-1.7
institution:       French Weather Service - Toulouse
history:          2021-11-13T18:08:50 GRIB to CDM+CF via cfgrib-0...
```

```
[13]: ds = cml.load_dataset(
        "meteonet-samples-weather-models", model="arpege", variable="P_sea_level"
    )
```

```
[14]: cml.plot_map(ds[0])
```




## Masks

```
[15]: ds = cml.load_dataset("meteonet-samples-masks", domain="SE")
```

```
[16]: cml.plot_map(ds[0])
```



```
[17]: cml.plot_map(ds[1])
```



You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab matplotlib
```

### 1.4.11 WeatherBench

This is an attempt to reproduce this research: <https://arxiv.org/abs/2002.00469>. There is a notebook available at: <https://binder.pangeo.io/v2/gh/pangeo-data/WeatherBench/master?filepath=quickstart.ipynb>

```
[2]: import matplotlib.pyplot as plt
```

```
[3]: import climetlab as cml
```

```
[ ]: ds = cml.load_dataset("weather-bench")
```

```
[5]: ds
```

```
[5]: <climetlab.datasets.weather_bench.WeatherBench at 0x7f621c0638b0>
```

```
[6]: print(ds.citation)
```

```
@article{rasp2020weatherbench,
    title={WeatherBench: A benchmark dataset for data-driven weather forecasting},
    author={Rasp, Stephan and Dueben, Peter D and Scher, Sebastian and Weyn,
        Jonathan A and Mouatadid, Soukayna and Thuerey, Nils},
```

(continues on next page)

(continued from previous page)


```
journal={arXiv preprint arXiv:2002.00469},  
year={2020}  
}
```

```
[7]: z500 = ds.to_xarray()
```

```
[8]: z500
```


```
[8]: <xarray.Dataset>  
Dimensions: (lat: 32, lon: 64, time: 350640)  
Coordinates:  
    level    int32 500  
    * lon      (lon) float64 0.0 5.625 11.25 16.88 ... 337.5 343.1 348.8 354.4  
    * lat      (lat) float64 -87.19 -81.56 -75.94 -70.31 ... 75.94 81.56 87.19  
    * time     (time) datetime64[ns] 1979-01-01 ... 2018-12-31T23:00:00  
Data variables:  
    z        (time, lat, lon) float32 dask.array<chunksize=(8760, 32, 64), meta=np.  
    ~ndarray>  
Attributes:  
    Conventions: CF-1.6  
    history:    2019-11-10 20:33:23 GMT by grib_to_ncdf-2.14.0: /opt/ecmwf...
```

```
[9]: cml.plot_map(z500)
```




```
[10]: z500.z.isel(time=0).plot()
```

```
[10]: <matplotlib.collections.QuadMesh at 0x7f62146b2cd0>
```




```
[11]: cml.plot_map(z500.z.isel(time=0))
```




```
[12]: climatology = z500.sel(time=slice("2016", "2016")).mean("time").load()
```

```
[13]: climatology.z.plot()
```

```
[13]: <matplotlib.collections.QuadMesh at 0x7f62145059a0>
```



[14]: `cml.plot_map(climatology.z)`



[15]: `climatology.z`

```
[15]: <xarray.DataArray 'z' (lat: 32, lon: 64)>
array([[48765.18, 48774.066, 48782.83, ..., 48745.145, 48750.582,
       48757.645],
       [48755.164, 48798.348, 48845.02, ..., 48690.23, 48700.72,
       48721.727],
       [48890.742, 48941.703, 48997.42, ..., 48815.234, 48822.87,
       48850.105],
       ...,
       [52378.613, 52398.484, 52420.074, ..., 52361.254, 52363.426,
       52366.344],
```

(continues on next page)

(continued from previous page)

```
[51937.207, 51943.78 , 51950.414, ..., 51906.508, 51919.223,
 51928.72 ],
[51565.38 , 51571.426, 51578.15 , ..., 51543.97 , 51551.11 ,
 51558.305]], dtype=float32)
```

Coordinates:

level	int32	500
* lon	(lon)	float64 0.0 5.625 11.25 16.88 ... 337.5 343.1 348.8 354.4
* lat	(lat)	float64 -87.19 -81.56 -75.94 -70.31 ... 75.94 81.56 87.19

You can run this notebook in , in , in

[55]: !pip install --quiet climetlab matplotlib

```
DEPRECATION: Configuring installation scheme with distutils config files is deprecated,
and will no longer work in the near future. If you are using a Homebrew or Linuxbrew
Python, please see discussion at https://github.com/Homebrew/homebrew-core/issues/76621
DEPRECATION: Configuring installation scheme with distutils config files is deprecated,
and will no longer work in the near future. If you are using a Homebrew or Linuxbrew
Python, please see discussion at https://github.com/Homebrew/homebrew-core/issues/76621
```

### 1.4.12 NOAA's hurricane database

[56]: import climetlab as cml

[57]: atlantic = cml.load\_dataset("hurricane-database", bassin="atlantic")

Get the Pandas frame

[58]: df = atlantic.to\_pandas()

[59]: df.bassin.unique()

[59]: array(['AL'], dtype=object)

#### Hurricanes making landfall at category 5

[60]: df[(df.category == 5) & (df.type == "L")]

bassin	number	year	name	time	type	status	lat	\
17942	AL	3	1935	unnamed	1935-09-03 02:00:00	L	HU	24.8
24300	AL	10	1955	janet	1955-09-27 17:00:00	L	HU	17.4
24303	AL	10	1955	janet	1955-09-28 05:00:00	L	HU	18.4
28888	AL	9	1969	camille	1969-08-18 04:00:00	L	HU	30.3
36448	AL	8	1988	gilbert	1988-09-14 15:00:00	L	HU	20.7
37967	AL	4	1992	andrew	1992-08-23 21:00:00	L	HU	25.4
37971	AL	4	1992	andrew	1992-08-24 08:40:00	L	HU	25.5
37972	AL	4	1992	andrew	1992-08-24 09:05:00	L	HU	25.5
45134	AL	4	2007	dean	2007-08-21 08:30:00	L	HU	18.7
45182	AL	6	2007	felix	2007-09-04 12:00:00	L	HU	14.3

(continues on next page)

(continued from previous page)

49925	AL	11	2017	irma	2017-09-06 05:45:00	L	HU	17.7
49927	AL	11	2017	irma	2017-09-06 11:15:00	L	HU	18.1
49929	AL	11	2017	irma	2017-09-06 16:30:00	L	HU	18.5
49941	AL	11	2017	irma	2017-09-09 03:00:00	L	HU	22.3
50139	AL	15	2017	maria	2017-09-19 01:15:00	L	HU	15.4
50835	AL	14	2018	michael	2018-10-10 17:30:00	L	HU	30.0
lon	knots	category	pressure					
17942	-80.8	160.0		5	892.0			
24300	-83.9	140.0		5	NaN			
24303	-87.8	150.0		5	914.0			
28888	-89.4	150.0		5	900.0			
36448	-87.0	140.0		5	900.0			
37967	-76.6	140.0		5	923.0			
37971	-80.2	145.0		5	926.0			
37972	-80.3	145.0		5	922.0			
45134	-87.7	150.0		5	905.0			
45182	-83.2	140.0		5	934.0			
49925	-61.8	155.0		5	914.0			
49927	-63.1	155.0		5	914.0			
49929	-64.4	155.0		5	915.0			
49941	-77.9	145.0		5	924.0			
50139	-61.3	145.0		5	922.0			
50835	-85.5	140.0		5	919.0			

## Get the track for Katrina

```
[61]: katrina = df[(df.name == "katrina") & (df.year == 2005)]
```

```
[62]: katrina
```

bassin	number	year	name	time	type	status	lat	\
44065	AL	12	2005	katrina 2005-08-23 18:00:00		TD	23.1	
44066	AL	12	2005	katrina 2005-08-24 00:00:00		TD	23.4	
44067	AL	12	2005	katrina 2005-08-24 06:00:00		TD	23.8	
44068	AL	12	2005	katrina 2005-08-24 12:00:00		TS	24.5	
44069	AL	12	2005	katrina 2005-08-24 18:00:00		TS	25.4	
44070	AL	12	2005	katrina 2005-08-25 00:00:00		TS	26.0	
44071	AL	12	2005	katrina 2005-08-25 06:00:00		TS	26.1	
44072	AL	12	2005	katrina 2005-08-25 12:00:00		TS	26.2	
44073	AL	12	2005	katrina 2005-08-25 18:00:00		TS	26.2	
44074	AL	12	2005	katrina 2005-08-25 22:30:00	L	HU	26.0	
44075	AL	12	2005	katrina 2005-08-26 00:00:00		HU	25.9	
44076	AL	12	2005	katrina 2005-08-26 06:00:00		HU	25.4	
44077	AL	12	2005	katrina 2005-08-26 12:00:00		HU	25.1	
44078	AL	12	2005	katrina 2005-08-26 18:00:00		HU	24.9	
44079	AL	12	2005	katrina 2005-08-27 00:00:00		HU	24.6	
44080	AL	12	2005	katrina 2005-08-27 06:00:00		HU	24.4	
44081	AL	12	2005	katrina 2005-08-27 12:00:00		HU	24.4	
44082	AL	12	2005	katrina 2005-08-27 18:00:00		HU	24.5	
44083	AL	12	2005	katrina 2005-08-28 00:00:00		HU	24.8	

(continues on next page)

(continued from previous page)

44084	AL	12	2005	katrina	2005-08-28	06:00:00	HU	25.2
44085	AL	12	2005	katrina	2005-08-28	12:00:00	HU	25.7
44086	AL	12	2005	katrina	2005-08-28	18:00:00	HU	26.3
44087	AL	12	2005	katrina	2005-08-29	00:00:00	HU	27.2
44088	AL	12	2005	katrina	2005-08-29	06:00:00	HU	28.2
44089	AL	12	2005	katrina	2005-08-29	11:10:00	L	HU 29.3
44090	AL	12	2005	katrina	2005-08-29	12:00:00	HU	29.5
44091	AL	12	2005	katrina	2005-08-29	14:45:00	L	HU 30.2
44092	AL	12	2005	katrina	2005-08-29	18:00:00	HU	31.1
44093	AL	12	2005	katrina	2005-08-30	00:00:00	TS	32.6
44094	AL	12	2005	katrina	2005-08-30	06:00:00	TS	34.1
44095	AL	12	2005	katrina	2005-08-30	12:00:00	TD	35.6
44096	AL	12	2005	katrina	2005-08-30	18:00:00	TD	37.0
44097	AL	12	2005	katrina	2005-08-31	00:00:00	EX	38.6
44098	AL	12	2005	katrina	2005-08-31	06:00:00	EX	40.1

	lon	knots	category	pressure
44065	-75.1	30.0	1	1008.0
44066	-75.7	30.0	1	1007.0
44067	-76.2	30.0	1	1007.0
44068	-76.5	35.0	1	1006.0
44069	-76.9	40.0	1	1003.0
44070	-77.7	45.0	1	1000.0
44071	-78.4	50.0	1	997.0
44072	-79.0	55.0	1	994.0
44073	-79.6	60.0	1	988.0
44074	-80.1	70.0	1	984.0
44075	-80.3	70.0	1	983.0
44076	-81.3	65.0	1	987.0
44077	-82.0	75.0	1	979.0
44078	-82.6	85.0	2	968.0
44079	-83.3	90.0	2	959.0
44080	-84.0	95.0	2	950.0
44081	-84.7	100.0	3	942.0
44082	-85.3	100.0	3	948.0
44083	-85.9	100.0	3	941.0
44084	-86.7	125.0	4	930.0
44085	-87.7	145.0	5	909.0
44086	-88.6	150.0	5	902.0
44087	-89.2	140.0	5	905.0
44088	-89.6	125.0	4	913.0
44089	-89.6	110.0	3	920.0
44090	-89.6	110.0	3	923.0
44091	-89.6	105.0	3	928.0
44092	-89.6	80.0	1	948.0
44093	-89.1	50.0	1	961.0
44094	-88.6	40.0	1	978.0
44095	-88.0	30.0	1	985.0
44096	-87.0	30.0	1	990.0
44097	-85.3	30.0	1	994.0
44098	-82.9	25.0	1	996.0

**Plot the track**[63]: `cml.plot_map(katrina, margins=0.25)`

## Retrieve matching fields from ERA5

```
[64]: hurricane = katrina[katrina.status == "HU"]
hurricane
```

	bassin	number	year	name	time	type	status	lat	\
44074	AL	12	2005	katrina	2005-08-25 22:30:00	L	HU	26.0	
44075	AL	12	2005	katrina	2005-08-26 00:00:00		HU	25.9	
44076	AL	12	2005	katrina	2005-08-26 06:00:00		HU	25.4	
44077	AL	12	2005	katrina	2005-08-26 12:00:00		HU	25.1	
44078	AL	12	2005	katrina	2005-08-26 18:00:00		HU	24.9	
44079	AL	12	2005	katrina	2005-08-27 00:00:00		HU	24.6	
44080	AL	12	2005	katrina	2005-08-27 06:00:00		HU	24.4	
44081	AL	12	2005	katrina	2005-08-27 12:00:00		HU	24.4	
44082	AL	12	2005	katrina	2005-08-27 18:00:00		HU	24.5	
44083	AL	12	2005	katrina	2005-08-28 00:00:00		HU	24.8	
44084	AL	12	2005	katrina	2005-08-28 06:00:00		HU	25.2	
44085	AL	12	2005	katrina	2005-08-28 12:00:00		HU	25.7	
44086	AL	12	2005	katrina	2005-08-28 18:00:00		HU	26.3	
44087	AL	12	2005	katrina	2005-08-29 00:00:00		HU	27.2	
44088	AL	12	2005	katrina	2005-08-29 06:00:00		HU	28.2	
44089	AL	12	2005	katrina	2005-08-29 11:10:00	L	HU	29.3	
44090	AL	12	2005	katrina	2005-08-29 12:00:00		HU	29.5	
44091	AL	12	2005	katrina	2005-08-29 14:45:00	L	HU	30.2	
44092	AL	12	2005	katrina	2005-08-29 18:00:00		HU	31.1	
	lon	knots	category	pressure					
44074	-80.1	70.0	1	984.0					
44075	-80.3	70.0	1	983.0					
44076	-81.3	65.0	1	987.0					
44077	-82.0	75.0	1	979.0					
44078	-82.6	85.0	2	968.0					
44079	-83.3	90.0	2	959.0					
44080	-84.0	95.0	2	950.0					
44081	-84.7	100.0	3	942.0					
44082	-85.3	100.0	3	948.0					
44083	-85.9	100.0	3	941.0					
44084	-86.7	125.0	4	930.0					
44085	-87.7	145.0	5	909.0					
44086	-88.6	150.0	5	902.0					
44087	-89.2	140.0	5	905.0					
44088	-89.6	125.0	4	913.0					
44089	-89.6	110.0	3	920.0					
44090	-89.6	110.0	3	923.0					
44091	-89.6	105.0	3	928.0					
44092	-89.6	80.0	1	948.0					

We can use the Pandas frame to specify the date and area of the request to the CDS.


```
[65]: source = cml.load_source(
    "cds",
    "reanalysis-era5-pressure-levels",
    variable="z",
    level=500,
```


(continues on next page)


(continued from previous page)


```
product_type="reanalysis",
time=[0, 6, 12, 18],
date=hurricane,
area=hurricane,
)


for s in source:
    cml.plot_map(s, width=400, grid=True)
```

















## Pacific basin


```
[66]: pacific = cml.load_dataset("hurricane-database", basin="pacific")
```


Get the Pandas frame


```
[67]: df = pacific.to_pandas()
```


Plot a few years

```
[68]: for year in range(2010, 2020):
    cml.plot_map(
        df[df.year == year], column="number", title=year, style="rainbow-markers"
    )
```










**Plot each track independently**

```
[69]: import matplotlib.pyplot as plt
```

```
[70]: cmap = plt.get_cmap("prism")
```

```
[71]: p = cml.new_plot(margins="5%")
i = 0
for year in range(1950, 1955):
    cp = df[(df.year == year) & (df.number == 1)]
    if len(cp):
        p.plot_map(cp, style={"+symbol_colour": cmap((i * 20) % cmap.N)})
    i += 1
p.show()
```



```
[ ]:
```

You can run this notebook in , in , in

```
[13]: !pip install --quiet climetlab
```

```
[14]: import climetlab as cml
```

```
[15]: r = {
    "class": "e2",
    "date": "1662-10-01/to/1663-12-31",
    "dataset": "icoads",
    "expver": "1608",
    "groupid": "17",
    "reportype": "16008",
    "format": "ascii",
    "stream": "oper",
    "time": "all",
    "type": "ofb",
}
```

```
source = cml.load_source("mars", **r)
```

```
[16]: pd = source.to_pandas()
```

[17]: pd

	expver@desc	type@desc	class@desc	stream@desc	andate@desc	\
0	'1608'	263	22	1025	16621015	
1	'1608'	263	22	1025	16621015	
2	'1608'	263	22	1025	16621015	
3	'1608'	263	22	1025	16621015	
4	'1608'	263	22	1025	16621016	
..	...	...	...	...	...	
673	'1608'	263	22	1025	16630425	
674	'1608'	263	22	1025	16630426	
675	'1608'	263	22	1025	16630426	
676	'1608'	263	22	1025	16630426	
677	'1608'	263	22	1025	16630426	
	antime@desc	seqno@hdr	reportype@hdr	bufrtype@hdr	subtype@hdr	...
0	120000	1	16008	1	11	...
1	120000	1	16008	1	11	...
2	120000	1	16008	1	11	...
3	120000	1	16008	1	11	...
4	120000	2	16008	1	11	...
..	...	...	...	...	...	
673	60000	25	16008	1	11	...
674	60000	26	16008	1	11	...
675	60000	26	16008	1	11	...
676	60000	26	16008	1	11	...
677	60000	26	16008	1	11	...
	entryno@body	obsvalue@body	varno@body	vertco_type@body	\	
0	1	158.000000	111	1		
1	2	2.600000	112	1		
2	3	-0.973977	41	1		
3	4	2.410678	42	1		
4	1	158.000000	111	1		
..	...	...	...	...		
673	4	2.155498	42	1		
674	1	124.000000	111	1		
675	2	6.700000	112	1		
676	3	-5.554552	41	1		
677	4	3.746593	42	1		
	vertco_reference_1@body	datum_status@body	bias_volatility@body	\		
0	0.0	1	Nan			
1	0.0	1	Nan			
2	0.0	1	Nan			
3	0.0	1	Nan			
4	0.0	1	Nan			
..	...	...	...			
673	0.0	1	Nan			
674	0.0	1	Nan			
675	0.0	1	Nan			
676	0.0	1	Nan			
677	0.0	1	Nan			


(continues on next page)

(continued from previous page)

```
an_depar@body  fg_depar@body  ppcode@conv_body
0             NaN          NaN          0
1             NaN          NaN          0
2             NaN          NaN          0
3             NaN          NaN          0
4             NaN          NaN          0
..
673            ...          ...
674            ...          ...
675            ...          ...
676            ...          ...
677            ...          ...

[678 rows x 44 columns]
```

```
[12]: cml.plot_map(pd, margins=2)
```



You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab climetlab-demo-source climetlab-demo-dataset
```

### 1.4.13 External plugins


```
[2]: import climetlab as cml
```

Get the demo dataset:

```
[3]: ds = cml.load_dataset("demo-dataset")
```

Plot it:

```
[4]: cml.plot_map(ds)
```



### External data source

```
[5]: !test -f test.db || wget https://github.com/ecmwf/climetlab/raw/main/docs/examples/test.  
db
```

```
[6]: s = cml.load_source(  
    "demo-source", "sqlite:///test.db", "select * from data;", parse_dates=["time"]  
)
```

```
[7]: df = s.to_pandas()
```

```
[8]: df
```

```
[8]:
```

	lat	lon	time	value
0	50.0	3.3	2001-01-01	4.9
1	51.0	-3.0	2001-01-02	7.3
2	50.5	-1.8	2001-01-03	5.5

```
[9]: cml.plot_map(df, margins=2)
```



You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab
```

```
[2]: %config Application.log_level="INFO"
```

#### 1.4.14 More plotting examples


```
[3]: import climetlab as cml
```

Get some GRIB data

```
[4]: ds = cml.load_dataset("sample-grib-data")
```


Plot the first field

```
[5]: cml.plot_map(ds[0])
```




Plot the second field

```
[6]: cml.plot_map(ds[1])
```




Plot both fields on the same map

```
[7]: cml.plot_map((ds[0], ds[1]))
```




Alternative method:

```
[8]: p = cml.new_plot()  
p.plot_map(ds[0])  
p.plot_map(ds[1])  
p.show()
```




Switch off background map

[9]: `cml.plot_map(ds[1], background=False)`



Switch off both foreground and background


[10]: `cml.plot_map(  
 ds[1],  
 foreground=False,  
)`





## Projections


```
[11]: from climetlab.plotting import projections
```



```
[12]: for projection in projections():
    cml.plot_map(projection=projection, title=projection)
```


































## Low-level graphical attributes


```
[13]: cml.plotting_options(width=500)
```

```
[14]: atlantic = cml.load_dataset("hurricane-database", bassin="atlantic")
```


```
[15]: df = atlantic.to_pandas()
```

```
[16]: david = df[(df.name == "david")]
```


```
[17]: cml.plot_map(  
    david, style=dict(symbol_colour="blue", symbol_type="marker", symbol_marker_index=3)  
)
```




```
[18]: cml.plot_map(david)
```




```
[19]: cml.plot_map(david, style={"+symbol_colour": "blue"})
```



```
[20]: cml.plot_map(
    david,
    background={
        "map_coastline_land_shade": True,
        "map_coastline_land_shade_colour": "green",
    },
)
```



```
[21]: cml.plot_map(david, background=False)
```



You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab
```

```
[2]: import climetlab as cml
```

```
[3]: source = cml.load_source(  
    "cds",  
    "insitu-observations-gruan-reference-network",  
    variable="air_temperature",  
    year="2017",  
    month="01",  
    day=[  
        "01",  
        "02",  
        "03",  
        "04",  
        "05",  
        "06",  
        "07",  
        "08",  
        "09",  
        "10",  
        "11",  
        "12",  
        "13",  
        "14",  
        "15",  
        "16",  
        "17",  
        "18",  
        "19",  
        "20",  
        "21",  
        "22",  
        "23",  
        "24",  
        "25",  
        "26",  
        "27",  
        "28",  
        "29",  
        "30",  
        "31"])
```

(continues on next page)

(continued from previous page)

```

    "11",
    "12",
    "13",
    "14",
    "15",
    "16",
    "17",
    "18",
    "19",
    "20",
    "21",
    "22",
    "23",
    "24",
    "25",
    "26",
    "27",
    "28",
    "29",
    "30",
    "31",
],
format="csv-lev.zip",
)

```

[4]: df = source.to\_pandas()

[5]: df

	station_name	report_timestamp	time_since_launch	report_id	\
0	LIN	2017-01-01 00:00:00+00:00	0.00000	242982	
1	LIN	2017-01-01 00:00:00+00:00	1.00000	242982	
2	LIN	2017-01-01 00:00:00+00:00	2.00000	242982	
3	LIN	2017-01-01 00:00:00+00:00	3.00012	242982	
4	LIN	2017-01-01 00:00:00+00:00	4.00012	242982	
...	...	...	...	...	...
1645953	LIN	2017-01-31 18:00:00+00:00	5002.16000	246127	
1645954	LIN	2017-01-31 18:00:00+00:00	5003.16000	246127	
1645955	LIN	2017-01-31 18:00:00+00:00	5004.16000	246127	
1645956	LIN	2017-01-31 18:00:00+00:00	5005.16000	246127	
1645957	LIN	2017-01-31 18:00:00+00:00	5006.16000	246127	
	longitude	latitude	height_of_station_above_sea_level	air_pressure	\
0	14.1203	52.2094	103.8	101096.00	
1	14.1203	52.2094	103.8	101019.00	
2	14.1204	52.2094	103.8	100946.00	
3	14.1204	52.2095	103.8	100879.00	
4	14.1204	52.2095	103.8	100810.00	
...	...	...	...	...	...
1645953	14.3240	51.9910	103.8	2354.49	
1645954	14.3247	51.9909	103.8	2352.38	
1645955	14.3253	51.9909	103.8	2350.24	

(continues on next page)


(continued from previous page)

1645956	14.3260	51.9908	103.8	2347.39
1645957	14.3267	51.9907	103.8	2344.79

	air_pressure_total_uncertainty	air_temperature
0	36.8895	274.357
1	36.8886	274.321
2	36.8878	274.282
3	36.8870	274.255
4	36.8861	274.257
...	...	...
1645953	37.2003	198.804
1645954	37.1999	198.776
1645955	37.1994	198.747
1645956	37.1988	198.710
1645957	37.1982	198.670

[1645958 rows x 10 columns]

[6]: `cml.plot_map(df[(df.time_since_launch == 0)])`



You can run this notebook in , in , in

[ ]: `!pip install --quiet climetlab[interactive]`

### 1.4.15 Interactive maps

[4]: `import climetlab as cml`

[5]: `atlantic = cml.load_dataset("hurricane-database", basin="atlantic")  
df = atlantic.to_pandas()  
katrina = df[(df.name == "katrina") & (df.year == 2005)]  
cml.interactive_map(katrina)`

[5]: `<IPython.core.display.HTML object>`

[ ]:

```
You can run this notebook in , in , in
```

[ ]: !pip install --quiet climetlab

#### 1.4.16 Creating a shared dataset of GRIBs

[1]: import climetlab as cml

##### Download data to the climetlab cache

```
[ ]: for month in range(1, 13): # This takes a few minutes.
    cml.load_source(
        "mars",
        param=["2t"],
        levtype="sfc",
        area=[50, -50, 20, 50],
        grid=[1, 1],
        date=f"2012-{month}",
    )
```

```
[ ]: cml.load_source(
    "mars",
    param="msl",
    levtype="sfc",
    area=[50, -50, 20, 50],
    grid=[1, 1],
    date="2012-12-01",
);
```

##### Export the data to a shared directory

This is optional, you could keep working on the data from the cache if you are the only user of the data and you do not mind redownloading it later. Other people should not use your cache:

- When using climetlab the cache will eventually fills up and the data may be deleted automatically,
- You will need to deal with permissions issues.
- It will make it difficult to share the data with other people.

Let us export the data to a shared directory `shared-data/temperature-for-analysis`

```
[4]: # Some housekeeping
!rm -rf shared-data/temperature-for-analysis
!mkdir -p shared-data/temperature-for-analysis
```

```
[5]: # export all data from my cache which is from mars and not older than 1 day
!climetlab export_cache shared-data/temperature-for-analysis --newer 1h --match mars
```

```
Copying cache entries matching 'mars' and newer than '2023-03-11 13:29:29' to shared-
→data/temperature-for-analysis.
100%|| 13/13 [00:00<00:00, 367.98it/s]
Copied 13 cache entries to shared-data/temperature-for-analysis.
```

### Create indexes to speed up data access when using it. (Optional)

```
[ ]: !climetlab index_directory shared-data/temperature-for-analysis
```

```
[ ]: !climetlab availability shared-data/temperature-for-analysis
```

### Using the data

```
[18]: DATA = "shared-data/temperature-for-analysis"
```

```
[19]: source = cml.load_source("indexed-directory", DATA)
```

```
[20]: source.availability
```

```
[20]: class=od, domain=g, expver=0001, levtype=sfc, md5_grid_
→section=ce1bd075c48ae7a5bf34f4e47166e942, step=0, stream=oper, time=1200, type=an
    date=20120101/to/20121231, param=2t
    date=20121201, param=msl
```

This is a good time to check the data, is all the data here? Are they missing dates? Parameters?

The data is ready to be used as numpy, tensorflow or xarray object.

```
[11]: source.sel(param="msl").to_numpy().mean()
```

```
[11]: 101725.47522756307
```

```
[22]: cml.load_source("indexed-directory", DATA, param="msl").to_numpy().mean()
```

```
[22]: 101725.47522756307
```

```
[23]: temp = source.sel(param="2t").order_by("date")
temp.to_tfdataset()
```

```
[23]: <PrefetchDataset element_spec=TensorSpec(shape=<unknown>, dtype=tf.float32, name=None)>
```

```
[24]: temp.to_xarray()
```

```
[24]: <xarray.Dataset>
```

```
Dimensions:      (number: 1, time: 366, step: 1, surface: 1, latitude: 31,
                  longitude: 101)
```

```
Coordinates:
```

* number	(number) int64 0
* time	(time) datetime64[ns] 2012-01-01T12:00:00 ... 2012-12-31T12:0...
* step	(step) timedelta64[ns] 00:00:00
* surface	(surface) float64 0.0

(continues on next page)

(continued from previous page)

```
* latitude      (latitude) float64 50.0 49.0 48.0 47.0 ... 23.0 22.0 21.0 20.0
* longitude    (longitude) float64 -50.0 -49.0 -48.0 -47.0 ... 48.0 49.0 50.0
  valid_time   (time, step) datetime64[ns] ...
Data variables:
  t2m          (number, time, step, surface, latitude, longitude) float32 ...
Attributes:
  GRIB_edition:      1
  GRIB_centre:       ecmf
  GRIB_centreDescription: European Centre for Medium-Range Weather Forecasts
  GRIB_subCentre:     0
  Conventions:        CF-1.7
  institution:       European Centre for Medium-Range Weather Forecasts
  history:           2023-03-11T14:35 GRIB to CDM+CF via cfgrib-0.9.1...
```

[25]: # Note that this is wrong (not implemented yet)  
temp.availability

[25]: class=od, domain=g, expver=0001, levtype=sfc, md5\_grid\_  
→section=ce1bd075c48ae7a5bf34f4e47166e942, step=0, stream=oper, time=1200, type=an  
date=20120101/to/20121231, param=2t  
date=20121201, param=msl

[ ]:

[ ]:

You can run this notebook in , in , in

### 1.4.17 Save data to GRIB

Here is an example of generating custom GRIB using climetlab.

To generate a GRIB, CliMetLab provides the function `cml.new_grib_output()`, requiring the following arguments:

- A numpy array containing the data to save.
- An object containing a template for the GRIB metadata, such as a CliMetLab source
- (Optional) A dictionary of metadata to override the template metadata.

Using this function is similar to `open(path)` in python, as shown below:

#### A template for the GRIB metadata

```
[1]: import climetlab as cml

s = cml.load_source(
  "cds",
  "reanalysis-era5-single-levels",
  variable=["2t", "msl"],
  product_type="reanalysis",
  area=[50, -50, 20, 50],
```

(continues on next page)

(continued from previous page)

```
date="2012-12-12",
time="12",
)

template = s[0] # temperature template
```

An numpy array with the data:


```
[2]: import numpy as np
import math

def generate_numpy_field(shape, ref=273.15, offset1=0, offset2=0):
    f = np.zeros(shape=shape, dtype=np.float64)
    for i in range(f.shape[0]):
        for j in range(f.shape[1]):
            f[i, j] = (
                ref
                + (math.sin((i + offset1) / 45.0) + math.sin((j + offset2) / 90.0)) * 15
            )
    return f

arr = generate_numpy_field(template.shape)
```

Let us plot the generated field for inspection. Notice how `cml.plot_map()` also uses the template to find the metadata required to plot the field as a temperature field.

```
[3]: cml.plot_map(arr, metadata=template)
```



## Write to GRIB


### Method 1

Compare to the usual python code:

```
f = open(path)
f.write(data)
f.close()
```

```
[4]: output = cml.new_grib_output("test1.grib", template=template)
output.write(arr)
output.close()
```

```
[5]: cml.plot_map(cml.load_source("file", "test1.grib"))
```




## Write to GRIB

### Method 2

The template can also be added in the `.write()` method instead of the `cml.new_grib_output()` function:

```
[6]: output = cml.new_grib_output("test2.grib")
output.write(arr, template=template)
output.close()
```

```
[7]: cml.plot_map(cml.load_source("file", "test2.grib"))
```



### Method 3

Compare to the usual python code:


```
with open(path) as f:
    f.write(data)
```

[8]:

```
with cml.new_grib_output("test3.grib", template=template) as output:
    output.write(arr)
```

[9]:

```
cml.plot_map(cml.load_source("file", "test3.grib"))
```



Once a GRIB output has been open, several fields can be written to it, as follows:

[10]:


```
with cml.new_grib_output("test4.grib", template=template) as output:
    for i in range(24):
        f = generate_numpy_field(template.shape, offset1=i, offset2=i)
        output.write(f, metadata={"time": i})
```


[11]:

```
test4 = cml.load_source("file", "test4.grib")

assert len(test4) == 24

cml.plot_map(test4[0])
cml.plot_map(test4[10])
cml.plot_map(test4[-1])
```





You can run this notebook in , in , in

```
[1]: !pip install --quiet climetlab
```

### 1.4.18 Dataset availability

(Work in progress)

```
[2]: from climetlab.utils.availability import Availability
from climetlab.decorators import availability
```

```
[3]: C0 = [
    {"level": "500", "param": "Z", "step": "24"}, 
    {"level": "500", "param": "Z", "step": "36"}, 
    {"level": "500", "param": "Z", "step": "48"}, 
    {"level": "500", "param": "T", "step": "24"}, 
    {"level": "500", "param": "T", "step": "36"}, 
    {"level": "500", "param": "T", "step": "48"}, 
    {"level": "850", "param": "T", "step": "36"}, 
    {"level": "850", "param": "T", "step": "48"}, 
    {"level": "1000", "param": "Z", "step": "24"}, 
    {"level": "1000", "param": "Z", "step": "48"},]
```

```
[4]: a0 = Availability(C0)
```

```
[5]: a0
```

```
[5]: <climetlab.utils.availability.Availability at 0x114a0ad60>
```

```
[6]: C1 = [
    {"level": "500", "param": "Z", "step": "24"}, 
    {"level": "500", "param": "Z", "step": "36"}, 
    {"level": "500", "param": "Z", "step": "48"}, 
    {"level": "500", "param": "T", "step": "24"}, 
    {"level": "500", "param": "T", "step": "36"}, 
    {"level": "500", "param": "T", "step": "48"}, 
    {"level": "850", "param": "T", "step": "36"}, 
    {"level": "850", "param": "T", "step": "48"}, 
    {"level": "1000", "param": "Z", "step": "24"}, 
    {"level": "1000", "param": "Z", "step": "48"}, 
    {"level": "850", "param": "Z", "step": "36"}, 
    {"level": "850", "param": "Z", "step": "48"}, 
]
```

```
[7]: a1 = Availability(C1)
```

```
[8]: a1
```

```
[8]: <climetlab.utils.availability.Availability at 0x10341e430>
```

```
[9]: a1.select(param="Z")
```

```
[9]: <climetlab.utils.availability.Availability at 0x114a0a790>
```

```
[10]: a1.select(param="T")
```

```
[10]: <climetlab.utils.availability.Availability at 0x114a2d0d0>
```

```
[11]: for r in a1.select(param="T").iterate():
    print(r)
{'param': ('T',), 'level': ('500',), 'step': ('24', '36', '48')}
{'param': ('T',), 'level': ('850',), 'step': ('36', '48')}
```

```
[12]: for r in a1.select(param="T").iterate(True):
    print(r)
```

```
{'param': 'T', 'level': '500', 'step': '24'}
{'param': 'T', 'level': '500', 'step': '36'}
{'param': 'T', 'level': '500', 'step': '48'}
{'param': 'T', 'level': '850', 'step': '36'}
{'param': 'T', 'level': '850', 'step': '48'}
```

```
[13]: a1.select(step="36")
```

```
[13]: <climetlab.utils.availability.Availability at 0x114a2daf0>
```

```
[14]: a1.select(step="36", param="T")
```

```
[14]: <climetlab.utils.availability.Availability at 0x114a2db20>
```

```
[15]: a1.count(step="36", param="T")
```

```
[15]: 2
```

```
[16]: a1.count()
```

```
[16]: 12
```

```
[17]: a1.select(step="22")
```

```
[17]: <climetlab.utils.availability.Availability at 0x114a2d7c0>
```

```
[18]: a1.select(param="Z", step="99").count()
```

```
[18]: 0
```

```
[19]: a3 = Availability(
    [
        {"date": ["1990-01-01/1990-01-02"], "param": ["Z", "T"]},
        {"date": ["1990-01-02/1990-01-05"], "param": ["Z"]},
        {"date": ["1990-01-04/1990-01-15"], "param": ["Z", "T"]},
    ],
    intervals=["date"],
)
```

```
[20]: a3
```

```
[20]: <climetlab.utils.availability.Availability at 0x114a2d460>
```

```
[21]: a3.count()
```

```
[21]: 29
```

```
[22]: a3.select(date="1990-01-02/1990-01-04")
```

```
[22]: <climetlab.utils.availability.Availability at 0x114a2d610>
```

```
[23]: for r in a3.select(date="1990-01-02/1990-01-04").iterate(True):
    print(r)

{'date': datetime.date(1990, 1, 2), 'param': 'T'}
{'date': datetime.date(1990, 1, 4), 'param': 'T'}
{'date': datetime.date(1990, 1, 2), 'param': 'Z'}
{'date': datetime.date(1990, 1, 3), 'param': 'Z'}
{'date': datetime.date(1990, 1, 4), 'param': 'Z'}
```

```
[24]: a3.missing(param="T", date="1990-01-01/1990-01-15")
```

```
[24]: <climetlab.utils.availability.Availability at 0x114a2dc10>
```

```
[ ]:
```

User Guide (TODO)

- *Howtos*
- *Datasets*
- *Data sources*
- *Data Manipulation*
- *Machine learning tools*
- *Plotting*
- *Caching*
- *Settings*
- *Using dask*
- *List of CliMetLab plugins*
- *Command line tool*

## 1.5 Howtos

### 1.5.1 How to install CliMetLab?

```
pip install climetlab
```

See the *installing instructions* for more details.

### 1.5.2 How to access data?

There are two ways to access data using CliMetLab:

- *Using a Dataset*: CliMetLab provides a few demo datasets. In order to access other datasets with `cml.load_dataset()`, the relevant plugin must be installed.
- *Using a data Source*: A data Source allows loading various kinds of data format and location through `cml.load_source()`. Data sources should be used when there is no dataset plugin for the data you are interested in.

### 1.5.3 How do I access data from this BUFR/GRIB/... file?

Use the *file* source.

### 1.5.4 How do I access data from this file on this unsupported format?

Write your own python code to open the file.

---

**Todo:** Add plugins and doc for readers.

---

### 1.5.5 How to help others to use my data ?

Creating a CliMetLab plugin can be a solution to share some code along with the dataset that you are publishing/using. See the [plugin documentation](#).

### 1.5.6 How to set up my CliMetLab cache directory ?

See [Caching](#).

### 1.5.7 How to share my cache directory with another user ?

It is not recommended to share your cache with others. What you are looking for may be a mirror. And this feature is not implemented yet.

A more robust approach is to put the data to a shared location, and define [a CliMetLab dataset](#) plugin to use it.

### 1.5.8 Can CliMetLab help using dask ?

See [Using dask](#).

## 1.6 Datasets

A **Dataset** is an object created using `cml.load_dataset(name, arg1, arg2=..., ...)` with the appropriate **name** and **arguments**, which provides access to a clearly well-defined **dataset**: these data have been defined and curated by somebody providing code along with the data. It also provides **metadata** and **additional functionalities**.

- The **name** is a string that uniquely identifies the dataset.
- The **argument(s)** `arg1` and keyword argument(s) `arg2` can be used to specify a subset of the dataset.
- The **data** can be accessed using methods such as `to_xarray()` or `to_pandas()` or other.
- Relevant **metadata** are attached directly to the dataset to provides additional information such as [an URL](#), [a citation](#), [licence](#), etc.
- **Additional functionalities:** When working on data, we are often writing code to transform, preprocess, adapt the data to our needs. While it may be very nice to understand deeply to deep magic under the hood, this process could be very time-consuming. Once somebody else did the hard work of preparing the data for a given purpose and designing relevant functions to process it, their code can be integrated and made available to others through a CliMetLab dataset plugin. The Dataset object is an instance of a Python class in which the plugin maintainers/users can share additional code.

---

**Note:** [Dataset](#) objects differ from data [Source](#) objects, as Datasets refer to a given set of data (such as “the 2m temperature on Europe in 2015”, while Sources are more generic such as “url”).

---

CliMetLab has build-in datasets (as examples) and most of the datasets are available as plugins (non-exhaustive [list of CliMetLab plugins](#)).

### 1.6.1 How to load a dataset?

The relevant plugin must be installed first, using pip.

```
pip install climetlab-demo-dataset
```

This ensures that the dataset can be loaded with `climetlab.load_dataset()`.

```
>>> import climetlab as cml  
>>> ds = cml.load_dataset("demo-dataset")
```

The first argument is the name of the dataset. It is used to find the relevant plugin and class to use. Other arguments are defined by the plugin maintainer and are documented in the plugin documentation (see [List of CliMetLab plugins](#)).

The Dataset object provides methods to access and use its data such as `to_xarray()` or `to_pandas()` or `to_numpy()` (there are other *methods that can be used to access data* from a Dataset).

```
>>> ds.to_xarray() # for gridded data  
>>> ds.to_pandas() # for non-gridded data  
>>> ds.to_numpy() # When the data is a n-dimensional array.  
>>> ds.to_tfrecord() # Experimental
```

---

**Note:** The name of the python package for a CliMetLab plugin usually starts with “climetlab-“.

---

**Note:** The plugin name does not necessarily match the dataset name, and one plugin can provide several datasets. As an example, the plugin `climetlab-s2s-ai-challenge` provides the datasets `s2s-ai-challenge-training-input` and `s2s-ai-challenge-training-output`:

```
>>> !pip install climetlab-s2s-ai-challenge  
>>> climetlab.load_dataset("s2s-ai-challenge-training-input", ...)  
>>> climetlab.load_dataset("s2s-ai-challenge-training-output", ...)
```

---

### 1.6.2 Xarray for gridded data

Gridded data typically are field data such as temperature or wind from climate or weather models or satellite images.

```
>>> import climetlab as cml  
>>> ds = cml.load_dataset("demo-dataset")  
>>> ds.to_xarray()  
<xarray.Dataset>  
Dimensions: (latitude: 181, longitude: 360)  
Coordinates:  
  * longitude (longitude) float64 -180.0 -179.0 -178.0 ... 177.0 178.0 179.0  
  * latitude (latitude) float64 90.0 89.0 88.0 87.0 ... -88.0 -89.0 -90.0  
Data variables:  
  t2m (latitude, longitude) float64 273.1 273.3 273.5 ... 250.7 250.6
```

### 1.6.3 Pandas for non-gridded data

None-gridded data typically is tabular non-structured data such as observations. It often includes a column for the latitude and longitude of the data.

```
>>> import climetlab as cml
>>> ds = cml.load_dataset("dataset-name", **options)
>>> ds.to_pandas()
```

### 1.6.4 Metadata attached to a dataset

Metadata attached to a dataset include the following.

**home\_page**: A link to the home page related to the dataset.  
**licence**: A link to the licence of the dataset.  
**documentation**: A link to the documentation related to the dataset.  
**citation**: A citation related to the dataset.  
**terms\_of\_use**: A text or link to the terms of use of the data.

```
>>> import climetlab as cml
>>> ds = cml.load_dataset("demo-dataset")
>>> ds.home_page
'https://github.com/ecmwf/climetlab-demo-dataset'
>>> ds.documentation
'Generates a dummy temperature field'
```

### 1.6.5 Best practices

---

**Note:** When sharing a python notebook, it is a good practice to add `!pip install climetlab-...` at the top of the notebook. If the package is not installed, CliMetLab fails with a `NameError` exception.

```
>>> # if the package climetlab-demo-dataset is not installed
>>> import climetlab as cml
>>> ds = cml.load_dataset("demo-dataset")
NameError: Cannot find dataset 'demo-dataset' (values are: ...),
```

```
>>> !pip install climetlab_demo_dataset --quiet
>>> import climetlab as cml
>>> ds = cml.load_dataset("demo-dataset")
>>>
```

---

There is no need to import the plugin package to enable loading the dataset:

```
>>> import climetlab_demo_dataset # Not needed
```

## 1.7 Data sources

### 1.7.1 What is a data Source?

A data **Source** is an object created using `cml.load_source(name, *args, **kwargs)` with the appropriate name and arguments, which provides access to the data.

A Source also provides metadata and additional functionalities:

- The source **name** is a string that uniquely identifies the source type.
- The **arguments** (`args` and `kwargs`) are used to specify the data location to access the data. They can include additional parameters to access the data.
- The **additional functionalities** include python code related to caching, plotting and interacting with other data.

```
>>> import climetlab as cml
>>> source = cml.load_source(name, *args, **kwargs)
```

The Source object provides methods to access and use its data such as `to_xarray()` or `to_pandas()` or `to_numpy()` (there are other *methods that can be used to access data* from a data Source).

```
>>> source.to_xarray() # for gridded data
>>> source.to_pandas() # for non-gridded data
>>> source.to_numpy() # When the data is a n-dimensional array.
>>> source.to_tfrecord() # Experimental
```

---

**Note:** *Source* objects differ from data *Dataset* objects, as Datasets refer to a given set of data (such as “the 2m temperature on Europe in 2015”, while Sources are more generic such as “url”).

---

### 1.7.2 Which data Sources are available?

CliMetLab has built-in sources and additional sources can be made available *as plugins*.

Built-in data sources:

- *file* source: Load data from a file.
- *url* source: Load data from a URL.
- *url-pattern* source: Load data from list of URL created from a pattern.
- *cds* source: Load data from the Copernicus Data Store (CDS).
- *mars* source: Load data from the Meteorological Archival and Retrieval System at ECMWF (MARS).
- *multi (advanced usage)* source: Aggregate multiple sources.
- *zenodo* source (experimental): Load data from Zenodo.
- *indexed\_urls* source (experimental): Load data from GRIB urls with partial download.

### 1.7.3 file

The simplest data source is the "file" source that accesses a local file.

```
>>> import climetlab as cml
>>> data = cml.load_source("file", "path/to/file")
>>> data.to_xarray() # for gridded data fields
>>> data.to_pandas() # for non-gridded data
```

*CliMetLab* will inspect the content of the file to check for any of the supported data formats listed below:

- **Fields:**
  - NetCDF
  - GRIB (see *GRIB support*)
- **Observations:**
  - CSV (comma-separated values)
  - BUFR (<https://en.wikipedia.org/wiki/BUFR>)
  - ODB (a bespoke binary format for observations)
- **Archive formats:** When given an archive format such as .zip, .tar, .tar.gz, etc, *CliMetLab* will attempt to open it and (recursively) extract any usable file.

```
>>> import climetlab as cml
>>> data = cml.load_source("url",
                           "https://www.example.com/data.tgz",
                           unpack=False)
```

---

**Todo:** Support for additionnal formats could be implemented as plugins.

---

### GRIB file example

```
>>> import climetlab as cml
>>> data = cml.load_source("file", "examples/test.grib")
>>> data.to_xarray()
<xarray.Dataset>
Dimensions:    (number: 1, time: 1, step: 1, surface: 1, latitude: 11, longitude: 19)
Coordinates:
* number      (number) int64 0
* time        (time) datetime64[ns] 2020-05-13T12:00:00
* step         (step) timedelta64[ns] 00:00:00
* surface      (surface) float64 0.0
* latitude     (latitude) float64 73.0 69.0 65.0 61.0 ... 45.0 41.0 37.0 33.0
* longitude    (longitude) float64 -27.0 -23.0 -19.0 -15.0 ... 37.0 41.0 45.0
  valid_time   (time, step) datetime64[ns] ...
Data variables:
  t2m          (number, time, step, surface, latitude, longitude) float32 ...
  msl          (number, time, step, surface, latitude, longitude) float32 ...
```

(continues on next page)

(continued from previous page)

```
Attributes:
  GRIB_edition:          1
  GRIB_centre:           ecmf
  GRIB_centreDescription: European Centre for Medium-Range Weather Forecasts
  GRIB_subCentre:         0
  Conventions:            CF-1.7
  institution:           European Centre for Medium-Range Weather Forecasts
  history:                2022-02-08T10:50 GRIB to CDM+CF via cfgrib-0.9.1...
  ↵ .
```

## NetCDF file example

```
>>> import climetlab as cml
>>> data = cml.load_source("file", "examples/test.nc")
>>> data.to_xarray()
<xarray.Dataset>
Dimensions:   (number: 1, time: 1, step: 1, surface: 1, latitude: 11, longitude: 19)
Coordinates:
  * number      (number) int64 0
  * time        (time) datetime64[ns] 2020-05-13T12:00:00
  * step        (step) timedelta64[ns] 00:00:00
  * surface     (surface) float64 0.0
  * latitude    (latitude) float64 73.0 69.0 65.0 61.0 ... 45.0 41.0 37.0 33.0
  * longitude   (longitude) float64 -27.0 -23.0 -19.0 -15.0 ... 37.0 41.0 45.0
    valid_time  (time, step) datetime64[ns] ...
Data variables:
  t2m          (number, time, step, surface, latitude, longitude) float32 ...
  msl          (number, time, step, surface, latitude, longitude) float32 ...
Attributes:
  GRIB_edition:          1
  GRIB_centre:           ecmf
  GRIB_centreDescription: European Centre for Medium-Range Weather Forecasts
  GRIB_subCentre:         0
  Conventions:            CF-1.7
  institution:           European Centre for Medium-Range Weather Forecasts
  history:                2022-02-08T10:50 GRIB to CDM+CF via cfgrib-0.9.1...
  ↵ .
```

## Other format file example

If the format is supported, see the [Examples](#) notebooks for a working example.

If the format is not supported, additional code can be included in CliMetLab to support it.

---

**Todo:** Support for additionnal formats could be implemented as plugins.

---

## 1.7.4 url

The "url" data source is very similar to the "file" source.

This sources downloads the data from the specified address and stores it in the *cache*, then it operates similarly to the "file" source above. The supported data formats are the same as for the "file" source.

```
>>> import climetlab as cml
>>> data = cml.load_source("url", "https://www.example.com/data.csv")
```

When given an archive format such as .zip, .tar, .tar.gz, etc, *CliMetLab* will attempt to open it and extract any usable file. If you want to keep the downloaded file as is, pass `unpack=False` to the method.

```
>>> import climetlab as cml
>>> data = cml.load_source("url",
                           "https://www.example.com/data.tgz",
                           unpack=False)
```

## 1.7.5 url-pattern

The "url-pattern" data source will build urls from the pattern specified, using the other arguments to fill the pattern. Each argument can be a list to iterate and create the cartesian product of all lists. Then each url is downloaded and stored it in the *cache*. The supported download the data from the address data formats are the same as for the *file* and *url* data sources above.

```
import climetlab as cml

data = cml.load_source("url-pattern",
                      "https://www.example.com/data-{foo}-{bar}-{qux}.csv",
                      foo = [1, 2, 3],
                      bar = ["a", "b"],
                      qux = "unique"
)
```

The code above will download and process the data from the six following urls:

1. <https://www.example.com/data-1-a-unique.csv>
2. <https://www.example.com/data-2-a-unique.csv>
3. <https://www.example.com/data-3-a-unique.csv>
4. <https://www.example.com/data-1-b-unique.csv>
5. <https://www.example.com/data-2-b-unique.csv>
6. <https://www.example.com/data-3-b-unique.csv>

If the urls are pointing to archive format, the data will be unpacked by `url-pattern` according to the `unpack` argument, similarly to what the source `url` does (see above the `url` source).

Once the data have been properly downloaded [and unpacked] and cached. It can be accessed using `to_xarray()` or `to_pandas()`.

To provide a unique `xarray.Dataset` (or `pandas.DataFrame`), the different datasets are merged. The default merger strategy for field data is to use `xarray.open_mfdataset` from `xarray`. This can be changed by providing a custom merger to the `url-pattern` source. See [merging sources](#)

## 1.7.6 cds

The "cds" data source accesses the Copernicus Climate Data Store (CDS), using the `cdsapi` package. A typical `cdsapi` request has the following format:

```
import cdsapi

client = cdsapi.Client()

client.retrieve("dataset-name",
                {"parameter1": "value1",
                 "parameter2": "value2",
                 ...})
```

to perform the same operation with *CliMetLab*, use the following code:

```
import climetlab as cml

data = cml.load_source("cds",
                      "dataset-name",
                      {"parameter1": "value1",
                       "parameter2": "value2",
                       ...})
```

Data downloaded from the CDS is stored in the the `cache`.

To access data from the CDS, you will need to register and retrieve an access token. The process is described here.

For more information, see the CDS knowledge base.

## 1.7.7 mars

The "mars" source allows handling data from the Meteorological Archival and Retrieval System (MARS).

To figure out which data you need, or discover relevant data available on MARS, see the publicly accessible [MARS catalog](#) (or this [access restricted catalog](#)). Notice that various [datasets of interests](#) are also publicly available. To access data from the MARS, you will need to register and retrieve an access token. For a more extensive documentation about MARS, please refer to the [MARS documentation](#) (or its access from the internet through its [web API](#)).

```
from ecmwfapi import ECMWFDataServer

server = ECMWFDataServer()

client.retrieve(
    {"parameter1": "value1",
     "parameter2": "value2",
     ...
    })
```

to perform the same operation with *CliMetLab*, use the following code:

```
import climetlab as cml

data = cml.load_source("mars",
                      {"parameter1": "value1",
```

(continues on next page)

(continued from previous page)

```
"parameter2": "value2",
...
})
```

Data downloaded from MARS is stored in the the *cache*.

## Examples

See the *Examples* notebooks for a working example.

### 1.7.8 zenodo

Zenodo is a general-purpose open repository developed and operated by CERN. It allows researchers to deposit research papers, datasets, etc. For each submission, a persistent digital object identifier (DOI) is minted, which makes the stored items easily citeable.

The "zenodo" source provides access data from [zenodo.org](https://zenodo.org), including downloading, caching, etc.

```
>>> ds = load_source("zenodo", record_id=...)
```

#### Example

```
>>> import climetlab as cml
>>> def only_csv(path):
...     return path.endswith(".csv")
>>> source = cml.load_source("zenodo", record_id=5020468, filter=only_csv)
>>> source.to_pandas()
```

---

**Note:** Support for zenodo access is experimental.

---

### 1.7.9 indexed\_urls

```
>>> ds = load_source( "indexed-urls", index, request)
```

Experimental. See *GRIB support*.

### 1.7.10 multi (advanced usage)

```
>>> ds = load_source( "multi", source1, source2, ...)
```

---

**Todo:** add documentation on multi-source.

---

## 1.8 Data Manipulation

---

**Todo:** This section is a draft.

---

### 1.8.1 Methods provided by CliMetLab data objects

Methods provided by CliMetLab data objects (such as a Dataset, a data Source or a Reader): Depending on the data, some of these methods are or are not available.

A CliMetLab data object provides methods to access and use its data.

```
>>> source.to_xarray() # for gridded data
>>> source.to_pandas() # for non-gridded data
>>> source.to_numpy() # When the data is a n-dimensional array.
>>> source.to_tfrecord() # Experimental
```

---

**Todo:** Explain fields.to\_xarray() and obs.to\_pandas().

Explain data[0]

Add here more details about the .to\_... methods.

---

### 1.8.2 Iterating

When a CliMetLab data *source* or dataset provides a list of fields, it can be iterated over to access each field (in a given order see *below*).

Let us get a source of fields from the Climate Data Store (CDS) and iterate through the list, each element is a field.

```
>>> import climetlab as cml
>>> ds = cml.load_source(
        "cds",
        "reanalysis-era5-single-levels",
        param=["2t", "msl"],
        product_type="reanalysis",
        grid='5/5',
        date=["2012-12-12", "2012-12-13"],
        time=[600, 1200, 1800],
    )
>>> len(ds)
10

>>> for f in ds: print(f)
GribField(2t,None,20121212,600,0,0)
GribField(msl,None,20121212,600,0,0)
GribField(2t,None,20121212,1200,0,0)
GribField(msl,None,20121212,1200,0,0)
GribField(2t,None,20121212,1800,0,0)
```

(continues on next page)

(continued from previous page)

```
GribField(msl,None,20121212,1800,0,0)
GribField(2t,None,20121213,600,0,0)
GribField(msl,None,20121213,600,0,0)
GribField(2t,None,20121213,1200,0,0)
GribField(msl,None,20121213,1200,0,0)
GribField(2t,None,20121213,1800,0,0)
GribField(msl,None,20121213,1800,0,0)
```

### 1.8.3 Selection with [...]

When a CliMetLab data *source* or dataset provides a list of fields, it can be *iterated* over to access each field (in a given order see *below*).

A subset of the list can be created using the standard python list interface relying on brackets and slices.

```
>>> import climetlab as cml
>>> ds = cml.load_source(
    "cds",
    "reanalysis-era5-single-levels",
    param=["2t", "msl"],
    product_type="reanalysis",
    grid='5/5',
    date=["2012-12-12", "2012-12-13"],
    time=[600, 1200, 1800],
)

>>> len(ds)
10

>>> print(f[0])
GribField(2t,None,20121212,600,0,0)

>>> for f in ds[0:3]: print(f)
GribField(2t,None,20121212,600,0,0)
GribField(msl,None,20121212,600,0,0)
GribField(2t,None,20121212,1200,0,0)

>>> for f in ds[0:5:2]: print(f)
GribField(2t,None,20121212,600,0,0)
GribField(2t,None,20121212,1200,0,0)
GribField(2t,None,20121212,1800,0,0)
```

## 1.8.4 Selection with .sel()

When a CliMetLab data *source* or dataset provides a list of fields, it can be *iterated* over to access each field (in a given order see *below*).

The method `.sel()` allows filtering this list to **select a subset** of the list of fields.

For instance, the following examples shows how to select various subsets of fields from a list of fields. After selection the required list of fields, the selected data from this subset is available with the methods `.to_numpy()`, `.to_pytorch()`, `.to_xarray()`, etc...

This list of fields can be filtered to extract on the fields corresponding to the 2m-temperature parameter with `.sel(param="2t")`:

```
>>> import climetlab as cml
>>> ds = cml.load_source(
    "cds",
    "reanalysis-era5-single-levels",
    param=["2t", "msl"],
    product_type="reanalysis",
    grid='5/5',
    date=["2012-12-12", "2012-12-13"],
    time=[600, 1200, 1800],
)

>>> len(ds)
10

>>> subset = ds.sel(param="2t")
>>> len(subset)
6
>>> for f in subset:
GribField(2t,None,20121212,600,0,0)
GribField(2t,None,20121212,1200,0,0)
GribField(2t,None,20121212,1800,0,0)
GribField(2t,None,20121213,600,0,0)
GribField(2t,None,20121213,1200,0,0)
GribField(2t,None,20121213,1800,0,0)
```

This list of fields can be filtered to extract on the fields corresponding to 12h time with `.sel(time=1200)`:

```
>>> import climetlab as cml
>>> ds = cml.load_source(
    "cds",
    "reanalysis-era5-single-levels",
    param=["2t", "msl"],
    product_type="reanalysis",
    grid='5/5',
    date=["2012-12-12", "2012-12-13"],
    time=[600, 1200, 1800],
)

>>> len(ds)
10
>>> subset = ds.sel(time=1200)
```

(continues on next page)

(continued from previous page)

```
>>> len(subset)
4
>>> for f in subset:
GribField(2t,None,20121212,1200,0,0)
GribField(msl,None,20121212,1200,0,0)
GribField(2t,None,20121213,1200,0,0)
GribField(msl,None,20121213,1200,0,0)
```

Or both filters can be applied simultaneously with `.sel(param="2t", time=1200)`.

```
>>> import climetlab as cml
>>> ds = cml.load_source(
    "cds",
    "reanalysis-era5-single-levels",
    param=["2t", "msl"],
    product_type="reanalysis",
    grid='5/5',
    date=["2012-12-12", "2012-12-13"],
    time=[600, 1200, 1800],
)
>>> len(ds)
10
>>> subset = ds.sel(param="2t", time=1200)
>>> len(subset)
2
>>> for f in subset:
GribField(2t,None,20121212,1200,0,0)
GribField(2t,None,20121213,1200,0,0)
```

Filtering on multiple values is also possible by providing a list of values `.sel(param="2t", time=[600, 1200])`.

```
>>> import climetlab as cml
>>> ds = cml.load_source(
    "cds",
    "reanalysis-era5-single-levels",
    param=["2t", "msl"],
    product_type="reanalysis",
    grid='5/5',
    date=["2012-12-12", "2012-12-13"],
    time=[600, 1200, 1800],
)
>>> len(ds)
10
>>> subset = ds.sel(param="2t", time=[600, 1200])
>>> len(subset)
4
>>> for f in subset:
GribField(2t,None,20121212,600,0,0)
GribField(2t,None,20121212,1200,0,0)
GribField(2t,None,20121213,600,0,0)
GribField(2t,None,20121213,1200,0,0)
```

### 1.8.5 Ordering with `.order_by()`

## 1.9 Merging Data sources

**Warning:** The merger functionality is experimental, the API may change.

---

**Todo:** add documentation on merging. `merge=concat()`. `merge=merge()`.

---

```
import climetlab as cml
import xarray as xr

class MyMerger():
    def __init__(self, *args, **kwargs):
        pass
    def merge(self, paths, **kwargs):
        return xr.open_mfdataset(paths)

data = cml.load_source("url-pattern",
    "https://www.example.com/data-{foo}-{bar}-{qux}.csv",
    foo = [1,2,3],
    bar = ["a", "b"],
    qux = "unique"
merger = MyMerger()
)
```

## 1.10 Machine learning tools

**Warning:** This part of CliMetLab is still a work in progress. Documentation and code behaviour will change.

---

**Todo:** TODO: Develop and document machine learning related tools

---

### 1.10.1 `to_tfdataset()`

To use a CliMetLab dataset with tensorflow, use the `_to_tfdataset()` method.

```
>>> import climetlab as cml
>>> ds = cml.load_dataset(x)
>>> x = ds.to_tfdataset(options)
>>> model.fit(x, ....)
```

The discussion is still open to decide whether `to_dataset()` returns:

- `tf.keras.utils.experimental.DatasetCreator`

- `tf.data.Dataset`
- `tf.keras.utils.Sequence`
- A custom CliMetLab class

## 1.10.2 PyTorch support

---

**Todo:** A long-term goal of CliMetLab is to provide an easy way to use a dataset with Pytorch. A merge request within this respect would be welcome. The CliMetLab API (exposed to the end-user) should be mostly identical for Tensorflow or Pytorch.

---

## 1.11 Plotting

See also : <https://confluence.ecmwf.int/display/MAGP/Reference+guide>

---

**Todo:** Introduce advance plotting options

---

```
import climetlab as cml

# cml.settings.set("plotting-options", {'dump_yaml': True})

dataset = cml.load_dataset("example-dataset")
data = dataset[0]

cml.plot_map(data, foreground=False)

cml.plot_map(data, foreground=True)

cml.plot_map(data, foreground="example-foreground")

cml.plot_map(
    data,
    foreground=dict(
        map_grid=False,
        map_label=False,
        map_grid_frame=True,
        map_grid_frame_thickness=5,
        map_boundaries=True,
    ),
)

# Partial update of the current `foreground`  

# How to do is still to be decided

# Option 1
cml.plot_map(
```

(continues on next page)

(continued from previous page)

```
data,
foreground={
    "+map_rivers": True,
    "+map_cities": True,
    "+map_label": True,
    "-map_boundaries": None,
},
)

# Option 2
cml.plot_map(
    data,
    foreground={
        "set": {"map_rivers": True, "map_cities": True, "map_label": True},
        "clear": ["map_boundaries"],
    },
)
# Option 3
cml.plot_map(
    data,
    foreground={
        "+": {"map_rivers": True, "map_cities": True, "map_label": True},
        "-": ["map_boundaries"],
    },
)
# Option 4
cml.plot_map(
    data,
    update_foreground={
        "map_rivers": True,
        "map_cities": True,
        "map_label": True,
        "map_boundaries": None,
    },
)
# Option 5
cml.plot_map(
    data,
    update={
        "foreground": {
            "map_rivers": True,
            "map_cities": True,
            "map_label": True,
            "map_boundaries": None,
        },
    },
)
```

```
import climetlab as cml

cml.plotting_options(width=400, foreground=False)
```

### 1.11.1 Projections

file\_content Traceback (most recent call last):

```
File "/home/docs/checkouts/readthedocs.org/user_builds/climetlab/checkouts/stable/climetlab/sphinxext/module_output.py"
    module.execute(*args)
```

```
File "/home/docs/checkouts/readthedocs.org/user_builds/climetlab/checkouts/stable/climetlab/sphinxext/file_content.py", l
    print(.. code-block::", LANGUAGES[ext])
```

KeyError: '.YAML'

See [mmap](#).

### 1.11.2 Styles

TODO

See [mcont](#) and [msymb](#).

### 1.11.3 Layers

See [mcoast](#).

TODO

## 1.12 Caching

**Warning:** This part of CliMetLab is still a work in progress. Documentation and code behaviour will change.

### 1.12.1 Purpose

CliMetLab caches most of the remote data access on a local cache. Running again `cml.load_dataset` or `cml.load_source` will use the cached data instead of downloading it again. When the cache is full, cached data is deleted according to its cache policy (i.e. oldest data is deleted first). CliMetLab cache configuration is managed through the CliMetLab [Settings](#).

**Warning:** The CliMetLab cache is intended to be used by a single user. Sharing cache with **multiple users is not recommended**. Downloading a local copy of data on a shared disk to have multiple users working is a different use case and should be supported through using mirrors. [Feedback and feature requests are welcome](#).

### 1.12.2 Cache location

The cache location is defined by the `cache-directory` setting. Its default value depends on your system:

- `/tmp/climetlab-$USER` for Linux,
- `C:\\\\Users\\\\$USER\\\\AppData\\\\Local\\\\Temp\\\\climetlab-$USER` for Windows
- `/tmp/.../climetlab-$USER` for MacOS

The cache location can be read and modified either with shell command or within python.

---

**Note:** It is recommended to restart your Jupyter kernels after changing the cache location.

---

From a shell with the `climetlab` command:

```
# Find the current cache directory
$ climetlab settings cache-directory
/tmp/climetlab-$USER

# Change the value of the setting
$ climetlab settings cache-directory /big-disk/climetlab-cache

# Cache directory has been modified
$ climetlab settings cache-directory
/big-disk/climetlab-cache
```

From a python notebook or python script:

```
>>> import climetlab as cml
>>> cml.settings.get("cache-directory") # Find the current cache directory
/tmp/climetlab-$USER
>>> # Change the value of the setting
>>> cml.settings.set("cache-directory", "/big-disk/climetlab-cache")

# Python kernel restarted

>>> import climetlab as cml
>>> cml.settings.get("cache-directory") # Cache directory has been modified
/big-disk/climetlab-cache
```

More generally, the CliMetLab settings can be read, modified, reset to their default values using the `climetlab` command or from python, see the [Settings documentation](#).

### 1.12.3 Cache limits

**Maximum-cache-size** The `maximum-cache-size` setting ensures that CliMetLab does not use too much disk space.

Its value sets the maximum disk space used by CliMetLab cache. When CliMetLab cache disk usage goes above this limit, CliMetLab triggers its cache cleaning mechanism before downloading additional data. The value of `cache-maximum-size` is absolute (such as “10G”, “10M”, “1K”).

**Maximum-cache-disk-usage** The `maximum-cache-disk-usage` setting ensures that CliMetLab leaves does not fill

your disk. Its values sets the maximum disk usage of the filesystem containing the cache directory. When the disk space goes below this limit, CliMetLab triggers its cache cleaning mechanism before downloading additional data. The value of `maximum-cache-disk-usage` is relative (such as “90%” or “100%”).

**Warning:** If your disk is filled by another application, CliMetLab will happily delete its cached data to make room for the other application as soon as it has a chance.

**Note:** When tweaking the cache settings, it is recommended to set the `maximum-cache-size` to a value below the user disk quota (if applicable) and `maximum-cache-disk-usage` to `None`.

#### 1.12.4 Caching settings default values

Name	Default	Description
<code>cache-directory</code>	<code>"/tmp/climetlab-docs"</code>	Directory of where the downloaded files are cached, with <code> \${USER} </code> is the user id. See <a href="#">Caching</a> for more information.
<code>maximum-cache-disk-usage</code>	<code>'90%'</code>	Disk usage threshold after which CliMetLab expires older cached entries (% of the full disk capacity). See <a href="#">Caching</a> for more information.
<code>maximum-cache-size</code>	<code>None</code>	Maximum disk space used by the CliMetLab cache (ex: 100G or 2T).

Other CliMetLab settings can be found [here](#).

## 1.13 Settings

*CliMetLab* is maintaining a set of global settings which control its behaviour.

The settings are saved in `~/.climetlab/settings.yaml`. They can be accessed from Python or using the `climetlab` command line.

### 1.13.1 Accessing settings

CliMetLab settings can be accessed using the python API:

```
import climetlab as cml

# Access one of the settings
cache_path = cml.settings.get("cache-directory")
print(cache_path)

# If this is the last line of a Notebook cell, this
```

(continues on next page)

(continued from previous page)

```
# will display a table with all the current settings
cml.settings
```

Or through the command line interface.

```
$ climetlab settings cache-directory
```

Or using the `climetlab` interactive prompt:

```
$ climetlab
(climetlab) settings cache-directory
```

## 1.13.2 Changing settings

---

**Note:** It is recommended to restart your Jupyter kernels after changing or resetting settings.

---

CliMetLab settings can be modified using the python API:

```
import climetlab as cml

# Change the location of the cache:
cml.settings.set("cache-directory", "/big-disk/climetlab-cache")

# Set some default plotting options (e.g. all maps will
# be 400 pixels wide by default):
cml.settings.set("plotting-options", width=400)
```

Or through the command line interface (CLI). Note that changing settings containing dictionary values is not possible with the CLI.

```
$ climetlab settings cache-directory /big-disk/climetlab-cache
```

Or using the `climetlab` interactive prompt:

```
$ climetlab
(climetlab) settings cache-directory /big-disk/climetlab-cache
```

## 1.13.3 Resetting settings

---

**Note:** It is recommended to restart your Jupyter kernels after changing or resetting settings.

---

CliMetLab settings can be reset using the python API:

```
import climetlab as cml

# Reset a named setting to its default value
cml.settings.reset("cache-directory")
```

(continues on next page)

(continued from previous page)

```
# Reset all settings to their default values
cml.settings.reset()
```

Or through the command line interface (CLI):

```
$ climetlab settings_reset cache-directory
$ climetlab settings_reset --all
```

Or using the `climetlab` interactive prompt:

```
$ climetlab
(climetlab) settings_reset
To wipe the cache completely, please use the --all flag. Use --help for more information.
(climetlab) settings_reset --all
(climetlab) Ctrl^D
```



### 1.13.4 Default values

Name	Default	Description
cache-directory	<code>/tmp/climetlab-docs</code>	Directory of where the downloaded files are cached, with \${USER} is the user id. See <a href="#">Caching</a> for more information.
check-out-of-date-urls	<code>True</code>	Perform a HTTP request to check if the remote version of a cache file has changed
dask-directories	<code>['/home/docs/.climetlab/dask']</code>	List of directories where to search for dask cluster definitions. See <a href="#">dask</a> for more information.
datasets-catalogs-urls	<code>['https://github.com/ecmwf-lab/climetlab-datasets/raw/main/datasets']</code>	List of url where to search for catalogues of datasets definitions. See <a href="#">Datasets</a> for more information.
datasets-directories	<code>['/home/docs/.climetlab/datasets']</code>	List of directories where to search for datasets definitions. See <a href="#">Datasets</a> for more information.
download-out-of-date-urls	<code>False</code>	Re-download URLs when the remote version of a cached file as been changed
layers-directories	<code>['/home/docs/.climetlab/layers']</code>	List of directories where to search for layers definitions. See <a href="#">Layers</a> for more information.
maximum-cache-disk-usage	<code>'90%'</code>	Disk usage threshold after which CliMetLab expires older cached entries (% of the full disk capacity). See <a href="#">Caching</a> for more information.
maximum-cache-size	<code>None</code>	Maximum disk space used by the CliMetLab cache (ex: 100G or 2T).
number-of-download-threads	<code>5</code>	Number of threads used to download data.
plotting-options	<code>{}</code>	Dictionary of default plotting options. See <a href="#">Plotting</a> for more information.
<b>1.13. Settings</b>		
projections-directories	<code>['/home/docs/.climetlab/projections']</code>	List of directories where to search for projections definitions. See <a href="#">Projections</a> for more information.

## 1.14 Using dask

### 1.14.1 Climetlab dask tools

You do not need CliMetLab to use *dask*. Dask is an independent python package often used with. to *xarray* and *pandas*. As CliMetLab seeks a strong integration to *dask*, some high-level functions may be useful to ease the interaction with dask.

---

**Todo:** This whole part about dask is EXPERIMENTAL, it will change in the future, may be removed or (very likely) moved to another package.

---

#### Start an local cluster and client

```
from climetlab.utils.dask import start
start('local')
# or $ climetlab dask start local
# or $ climetlab dask local --start
```

#### Start an ssh cluster and client

```
from climetlab.utils.dask import start
start('ssh')
```

#### Start a SLURM dask cluster and client

```
from climetlab.utils.dask import start
start('slurm')
```

#### Start a slurm dask cluster on HPC

This assumes that your HPC admin set up the hpc-name-config-1.yaml file on the appropriate location.

```
from climetlab.utils.dask import start
start('hpc-name-config-1')
```

#### Access the dask dashboard

---

**Todo:** Not implemented yet.

---

## Access the dask logs

---

**Todo:** Not implemented yet.

---

## Stop the dask cluster

The dask cluster and client will usually stop automatically when the python process ends. Nevertheless, it is possible to stop dask if it has been started from climetlab.

```
from climetlab.utils.dask import stop
stop()
```

### 1.14.2 Advanced dask usages

Note: In this section a “dask deployment” refers to a client and a cluster. It does not refers to a Cloud deployment using Kubernetes, etc.

#### Create a custom dask deployment specifications

Create the yaml file \$HOME/.climetlab/dask/hpc-name-config-1.yaml. Then use it with:

```
from climetlab.utils.dask import start
start('hpc-name-config-1')
```

---

**Todo:** This is EXPERIMENTAL.

---

---

**Note:** For HPC system admin: Adding yaml files in /opt/climetlab/dask/\*.yaml will give global access to all users.

---

#### Reuse the dask client

```
from climetlab.utils.dask import start
client = start('local').client
```

#### Scale the dask cluster

---

**Todo:** Define what “scale” mean in this context.

---

```
from climetlab.utils.dask import start
deploy = start('slurm')
deploy.scale(..)
```

## 1.15 List of CliMetLab plugins

---

**Note:** This list is **not exhaustive**. Some plugins are not listed here because we are not aware of them or because they are for internal use only, or not ready to be shared.

If you would like a plugin to be added in this list, please submit a pull request to CliMetLab or [open an issue on github](#).

---

### 1.15.1 Dataset plugins

Installing a *dataset* plugin, allows using an additional dataset in `cml.load_dataset`.

- [climetlab-s2s-ai-challenge](#): Providing data for the Sub-seasonal to Seasonal (S2S) Artificial Intelligence Challenge (<https://s2s-ai-challenge.github.io>)

Datasets provided: `s2s-ai-challenge-*`

- [climetlab-demo-dataset](#): Demo plugin to illustrate to dataset plugin mechanism.

Dataset provided: `demo-dataset`

- [climetlab-tropical-cyclone-dataset](#): Tropical cyclones. In progress.

Datasets provided: `tc-*`

- [climetlab-maelstrom-yr](#): Alpha. Gridded weather data for the Nordics, designed for ML postprocessing. Part of the [MAELSTROM](#) project.

Dataset provided: `maelstrom-yr`

- [climetlab-maelstrom-nogwd](#): Alpha. Dataset for learning non-orographic gravity wave parametrization. Part of the [MAELSTROM](#) project.

Dataset provided: `maelstrom-nogwd`

- [climetlab-maelstrom-radiation](#): Alpha. Dataset for learning radiative heating parametrization. Part of the [MAELSTROM](#) project.

Datasets provided: `maelstrom-radiation`, `maelstrom-radiation-tf`

- [climetlab-maelstrom-ens10](#): Alpha. Dataset for testing ensemble postprocessing techniques. Part of the [MAELSTROM](#) project.

Datasets provided: `maelstrom-ens5mini`, `maelstrom-ens10`

- [climetlab-maelstrom-downscaling](#): Alpha. Dataset for testing downscaling techniques. Part of the [MAELSTROM](#) project.

Dataset provided: `maelstrom-downscaling`

- [climetlab-maelstrom-power-production](#): Alpha. Dataset for predicting wind farm power production from weather data. Part of the [MAELSTROM](#) project.

Datasets provided: `maelstrom-power-production`, `maelstrom-weather-model-level`,  
`maelstrom-weather-pressure-level`, `maelstrom-weather-surface-level`,  
`maelstrom-constants-a-b`

## Drafts Dataset Plugins

- `climetlab-cems-flood`: Glofas data. In progress.  
Dataset provided: `glofas`
  - `climetlab-eumetnet-postprocessing-benchmark`:  
Eumetnet postprocessing benchmark dataset.
  - `climetlab-meteonet`: Meteonet dataset developed by Météo-France.
- 

## 1.15.2 Source plugins

Installing a `source` plugin, allows using an additional source in `cml.load_source`.

- `google-drive`  
Access public files in Google Drive with `cml.load_source("google-drive", file_id="...")`
- `climetlab-demo-source`  
Demo plugin to illustrate to source plugin mechanism.

## Drafts Source Plugins

- `stvl`  
Access data the STVL database with `cml.load_source("stvl", ...)`

## 1.16 Command line tool

Installing climetlab also make available the `climetlab` utility command line interface.

### 1.16.1 Usage

```
$ climetlab <command> [options]
```

```
$ climetlab
(climetlab) <command> [options]
```

### 1.16.2 Interactive prompt

`climetlab`

Running the `climetlab` command with no argument starts the interactive prompt. Autocompletion is enabled on the interactive prompt. To exit the interactive prompt use Control+D.

```
$ climetlab
(climetlab) <command> [options]
(climetlab)
```

### 1.16.3 availability

#### Usage

```
climetlab availability [-h] [--stdout] [--yaml] [--keys KEYS [KEYS ...]] source
```

Create json availability file.

#### Positional arguments

source ↳ of data	File or directory for describing a dataset or source. with GRIB data.
---------------------	--

#### options:

-h, --help	show this help message and exit
--stdout	Output to stdout (no file).
--yaml	Output yaml format.

**--keys KEYS [KEYS ...]** Keys to use in availability default is (param,time,date,step,levelist).

---

### 1.16.4 benchmark (experimental)

#### Usage

```
climetlab benchmark [-h] [--indexedurl] [--dataloading] [--nargs [NARGS ...]]  
↳ [--all]
```

Run predefined benchmarks, for CliMetLab development purposes.

#### options:

-h, --help	show this help message and exit
--indexedurl	Benchmark on using indexed URL (byte-range) and various servers.
--dataloading	Test loading some data.

**--nargs [NARGS ...]** --all Run all benchmarks.

---

## 1.16.5 cache

### Usage

```
climetlab cache [-h] [--json] [--all] [--path] [--sort KEY] [--reverse] [--match STRING]
                  [--newer DATE] [--older DATE] [--accessed] [--larger SIZE] [--smaller SIZE]
```

Cache command to inspect the CliMetLab cache. The selection arguments are the same as for the `climetlab decache` deletion command.

### Examples

```
climetlab cache --all
```

#### options:

<b>-h, --help</b>	show this help message and exit
<b>--json</b>	produce a JSON output

`--all` `--path` print the path of cache directory and exit  
`--sort KEY` sort output according to increasing values of KEY.  
`--reverse` reverse the order of the sort, from larger to smaller  
`--match STRING` TODO  
`--newer DATE` TODO  
`--older DATE` TODO  
`--accessed` use the date of last access instead of the creation date  
`--larger SIZE` consider only cache entries that are larger than SIZE bytes  
`--smaller SIZE` consider only cache entries that are smaller than SIZE bytes

SIZE can be expressed using suffixes such as K, M, G, etc. For example `--larger 1G` will match all cache entries larger than 1 GiB.

DATE can be expressed as absolute time like `2021-10-10T22:59:00` or relative such as 1h (one hour ago) or 2d (two days ago).

The `--older` and `--newer` consider the *creation date* of cache entries, unless `--accessed` is specified. In this case the time of *last access* is used.

Example, to remove large files not accessed for one week:

```
decache --accessed --older 1w --larger 1G
```

## 1.16.6 check (experimental)

### Usage

```
climetlab check [-h]
```

Experimental script to help debugging.

#### options:

<b>-h, --help</b>	show this help message and exit
-------------------	---------------------------------

## 1.16.7 completion

### Usage

```
climetlab completion [-h] [SHELL]
```

Enable autocompletion for the “climetlab” shell command.

Supported shells are : zsh bash.

**Usage:** climetlab completion

### Positional arguments

SHELL	Shell to use for autocompletion. Must be zsh or bash.
-------	---

**options:**

<b>-h, --help</b>	show this help message and exit
-------------------	---------------------------------

---

## 1.16.8 decache

### Usage

```
climetlab decache [-h] [--all] [--match STRING] [--newer DATE] [--older DATE]  
↳[--accessed]  
      [--larger SIZE] [--smaller SIZE]
```

Cache deletion command (decache) to clean the cache from selected files. The selection arguments are the same as for the `climetlab cache` query command.

**options:**

<b>-h, --help</b>	show this help message and exit
-------------------	---------------------------------

`--all` `--match STRING` TODO `--newer DATE` TODO `--older DATE` TODO `--accessed` use the date of last access instead of the creation date `--larger SIZE` consider only cache entries that are larger than SIZE bytes `--smaller SIZE` consider only cache entries that are smaller than SIZE bytes

SIZE can be expressed using suffixes such a K, M, G, etc. For example `--larger 1G` will match all cache entries larger than 1 GiB.

DATE can be expressed as absolute time like `2021-10-10T22:59:00` or relative such as `1h` (one hour ago) or `2d` (two days ago).

The `--older` and `--newer` consider the *creation date* of cache entries, unless `--accessed` is specified. In this case the time of *last access* is used.

Example, to remove large files not accessed for one week:

```
decache --accessed --older 1w --larger 1G
```

---

## 1.16.9 dump\_index

### Usage

```
climetlab dump_index [-h] filename
```

### Positional arguments

filename	Database filename.
----------	--------------------

#### options:

<b>-h, --help</b>	show this help message and exit
-------------------	---------------------------------

## 1.16.10 export\_cache

### Usage

```
climetlab export_cache [-h] [--match STRING] [--newer DATE] [--older DATE] [--accessed]
[--larger SIZE] [--smaller SIZE] [--permissions [PERMISSIONS ...]] DIRECTORY
```

Copy part of the cache content to a directory.

### Positional arguments

DIRECTORY	Output directory where to copy the cache content.
-----------	---

#### options:

<b>-h, --help</b>	show this help message and exit
<b>--match STRING</b>	TODO
<b>--newer DATE</b>	TODO
<b>--older DATE</b>	TODO
<b>--accessed</b>	use the date of last access instead of the creation date
<b>--larger SIZE</b>	consider only cache entries that are larger than SIZE bytes
<b>--smaller SIZE</b>	consider only cache entries that are smaller than SIZE bytes
<b>--permissions [PERMISSIONS ...]</b>	By default, the exported data is public and writable by its owner. --permissions read-only : Make the data public and read only. --permissions disabled : Do not tweak the files or directories permissions.

SIZE can be expressed using suffixes such a K, M, G, etc. For example `--larger 1G` will match all cache entries larger than 1 GiB.

DATE can be expressed as absolute time like `2021-10-10T22:59:00`` or relative such as `1h` (one hour ago) or `2d` (two days ago).

The `--older` and `--newer` consider the *creation date* of cache entries, unless `--accessed` is specified. In this case the time of *last access* is used.

Example, to remove large files not accessed for one week:

```
decache --accessed --older 1w --larger 1G
```

---

## 1.16.11 grib\_info

### Usage

```
climetlab grib_info [-h] [--param PARAM] [--json] [--stdin]
```

Display information about grib parameters.

#### options:

- |                      |   |
|----------------------|---|
| <b>-h, --help</b>    | show this help message and exit         |
| <b>--param PARAM</b> | Comma separated list of parameters.     |
| <b>--json</b>        | Long json output format.                |
| <b>--stdin</b>       | Using stdin as input (for bash piping). |
- 

## 1.16.12 index\_directory

### Usage

```
climetlab index_directory [-h] [--no-follow-links] [--relative-paths] [--  
  ↵output OUTPUT]  
                           directory
```

Index a directory containing GRIB files.

### Positional arguments

directory	Directory containing the GRIB files to index.
-----------	---

#### options:

- |                          |                                 |
|--------------------------|---------------------------------|
| <b>-h, --help</b>        | show this help message and exit |
| <b>--no-follow-links</b> | Do not follow symlinks.         |

---

<b>--relative-paths</b>	Use relative paths. Default is to use relative paths, except when a custom location is provided for the index location. (when the argument <code>--output</code> is used, default for <code>--relative-path</code> is False)
<b>--output OUTPUT</b>	Custom location of the database file, will write absolute filenames in the database.

---

## 1.16.13 index\_url

### Usage

```
climetlab index_url [-h] URL
```

Create json index files for remote Grib url.

### Positional arguments

URL	url to index
-----	--------------

#### options:

<b>-h, --help</b>	show this help message and exit
-------------------	---------------------------------

---

## 1.16.14 index\_urls

### Usage

```
climetlab index_urls [-h] [--baseurl BASEURL] URLs [URLS ...]
```

**Create json index files for remote Grib urls.** If the option `--baseurl` is provided, the given url are relative to the `BASEURL`. This allows creating an index for multiple grib.

### Positional arguments

URLS	List of urls to index.
------	------------------------

#### options:

<b>-h, --help</b>	show this help message and exit
-------------------	---------------------------------

<b>--baseurl BASEURL</b>	Base url to use as a prefix to happen on each URLs to build actual urls.
--------------------------	--

## 1.16.15 libraries

### Usage

```
climetlab libraries [-h] [--json]
```

#### options:

- |                   |                                 |
|-------------------|---------------------------------|
| <b>-h, --help</b> | show this help message and exit |
| <b>--json</b>     | produce a JSON output           |
- 

## 1.16.16 plugins

### Usage

```
climetlab plugins [-h] [--json]
```

List the available plugins

#### options:

- |                   |                                 |
|-------------------|---------------------------------|
| <b>-h, --help</b> | show this help message and exit |
| <b>--json</b>     | produce a JSON output           |
- 

## 1.16.17 settings

### Usage

```
climetlab settings [-h] [--json] [SETTING ...]
```

Display or change CliMetLab settings. See <https://climetlab.readthedocs.io/guide/settings.html> for more details.

### Examples

```
climetlab settings cache-directory /big-disk/climetlab-cache
```

### Positional arguments

```
SETTING
```

#### options:

- |                   |                                 |
|-------------------|---------------------------------|
| <b>-h, --help</b> | show this help message and exit |
| <b>--json</b>     | produce a JSON output           |
-

## 1.16.18 settings\_reset

### Usage

```
climetlab settings_reset [-h] [--all] [SETTING ...]
```

Display or change CliMetLab settings. See <https://climetlab.readthedocs.io/guide/settings.html> for more details.

### Examples

```
climetlab settings cache-directory /big-disk/climetlab-cache
```

### Positional arguments

```
SETTING
```

#### options:

- |                   |                                 |
|-------------------|---------------------------------|
| <b>-h, --help</b> | show this help message and exit |
| <b>--all</b>      | All settings                    |
- 

## 1.16.19 test\_data

### Usage

```
climetlab test_data [-h] [DIRECTORY]
```

Create a directory with data used to test climetlab.

### Positional arguments

```
DIRECTORY Shell to use for autocompletion. Must be zsh or bash.
```

#### options:

- |                   |                                 |
|-------------------|---------------------------------|
| <b>-h, --help</b> | show this help message and exit |
|-------------------|---------------------------------|
-

## 1.16.20 versions

### Usage

```
climetlab versions [-h] [--json] [--all] [PACKAGE ...]
```

List the versions of important Python packages.

### Positional arguments

PACKAGE	optional list of Python packages
---------	----------------------------------

#### options:

-h, --help	show this help message and exit
------------	---------------------------------

--json	produce a JSON output
--------	-----------------------

-all
------

### Plugin Developer Guide

- *Overview*
- *How to create a dataset plugin (pip)*
- *How to create a dataset plugin (YAML)*
- *How to create a source plugin*
- *Normalize decorator*
- *Availability decorator*
- *Alias argument decorator*
- *GRIB support*
- *Plotting*

## 1.17 Overview

“*CliMetLab provides a common place to share code used in the Weather and Climate community to pre-process data, plot it, and include additional tools, especially for machine learning purposes.*”

**Warning:** CliMetLab is still a work in progress: Backward compatibility is not ensured as long a version 1.0 is not released (see [todo list](#)). Nevertheless, the API and functionalities provided for the dataset and source plugins are **mostly** stable and already usable.

The **plugins developer guide** part of the CliMetLab documentation describes how to create plugins (or YAML files) to add data and functionalities to CliMetLab, to make it available to the end-users.

### 1.17.1 Sharing code using plugins

In order to avoid rewriting the same code over and over, consider distributing it, the design of CliMetLab allows this through plugins developed by data providers and data users and other stakeholders.

CliMetLab has several types of plugins.

- *Dataset plugin*
- *Sources plugin*
- Reader plugin (draft)
- Helper plugin (draft)
- Machine learning plugin (not yet implemented)

Depending on the functionalities provided by your code, it can be integrated in CliMetLab differently either as a dataset or a source or a reader or a helper plugin (please refer to the table below.) If you are distributing or referring to a dataset, the right plugin type for you is likely to be a *dataset plugin*.

For more details, here is also a general description of the *CliMetLab plugin mechanism*.

Plugin type	Use case	End-User API
<i>Dataset</i>	Sharing code to access a curated dataset optionally with additional functionalities.	<code>climetlab.load_dataset()</code>
<i>Source</i>	Sharing code to access a new type of location where there are data.	<code>climetlab.load_source()</code>
Reader (DRAFT)	Sharing code to read data on a given format, using specific conventions, or requiring conversions. Readers will be available to the code written for the sources.	<code>climetlab.load_source()</code>
Helper (DRAFT)	Sharing code related to plotting data, enhancing data with additional functionalities.	<code>climetlab.plot_map()</code>
Machine Learning (TODO)	Sharing weather and climate specific code related to machine learning.	<code>climetlab.Dataset</code> , <code>climetlab.Source</code>

### 1.17.2 How else can I contribute?

See the *todo list*.

## 1.18 How to create a dataset plugin (pip)

From the *end-user's perspective*, a **Dataset** is a object created using `cml.load_dataset(name, *args)` with the appropriate name and arguments, which provides data.

From the plugin's developer perspective, a **Dataset** is a Python class that inherits from the CliMetLab class `climetlab.Dataset`. This class contains the Python code providing specific helper functions and curated access to the data. Dataset can also be defined from *yaml files* if they have no specific Python code and rely on (yet to defined) standard conventions.

CliMetLab has build-in example datasets for demo purposes. And more examples can be found in the non-exhaustive *list of CliMetLab plugins*.

---

**Note: Naming convention**

- A plugin package name (pip) should preferably start with `climetlab-` and use dashes “-“.
  - The Python package to import should start with `climetlab_` and must use underscores “\_”.
  - A CliMetLab dataset defined by a plugin should start with the plugin name and must use dashes “-“.
- 

## 1.18.1 Blueprint

### Automatic creation script

While creating the package manually from the documentation and from the example above is possible, there is also a semi-automated way to generate a pip package from a template. The generated package has a predefined dataset and is ready to be shared on Github and distributed with pip.

```
$ pip install climetlab-plugin-tools
$ climetlab plugin_create_dataset
# Answer the questions
# Only the first question (plugin name) and the latest (licence) are required.
# Other have sensible default values.
```

Here is a `verbose` output of running the plugin creation script.

---

**Note:** “Unknown command `plugin_create_dataset`” This error happens if you have not installed the package `climetlab-plugin-tools`.

```
$ climetlab plugin_create_dataset
Unknown command plugin_create_dataset. Type help for the list of known command
names.
```

---

### Dataset names

The plugin mechanism relies on using `entry_points`. The three lines highlighted below are registering the class `climetlab_dataset_plugin.rain_observations:RainObservations` with `entry_points` to a CliMetLab dataset called `dataset-plugin-rain-observations`. The python plugin mechanism is exhaustively described in the [Python reference documentation](#) and here are more details about [how on CliMetLab uses it](#).

```
setuptools.setup(
    name="climetlab-dataset-plugin",
    version="0.0.1",
    description="Example climetlab external dataset plugin",

    entry_points={"climetlab.datasets":
        ["dataset-plugin-rain-observations=climetlab_dataset_plugin.rain_observations:
        RainObservations"]
    },
)
```

Once *entry\_point* has registered the class, the end-user can use this external plugin to access it

```
import climetlab as cml
cml.load_dataset("dataset-plugin-rain-observations")
```

## Automatic testing of the plugin

In the folder **tests** are set up automatic tests of the plugin using pytest. If the repository is hosted on github, the tests triggers automatically when pushing to the repository. Additionally, code quality is enabled using black, isort and flake.

All tests could be disabled or adapted in the `.github/workflows/` folder.

## Notebooks as documentation

The folder `notebooks` in each plugin can be used to store usage example or demo on how to use the data, such as this [notebook](#), Notebook are automatically tested if the repository is on github.

Links on the README file are pointing to binder, colab, etc. to run the automatically created notebook.

## Manually creating the Python package

Here is a minimal example of pip package defining a dataset plugin : <https://github.com/ecmwf/climetlab-demo-dataset>

### 1.18.2 Adapting plugin code

#### Renaming a dataset

The dataset name can be changed by changing the `setup.py` file.

```
- ["dataset-plugin-rain-observations=climetlab_dataset_plugin.rain_observations:
  ↵RainObservations"]
+ ["dataset-plugin-new-name           =climetlab_dataset_plugin.rain_observations:
  ↵RainObservations"]
```

A good practice is to change keep the class name in sync with the dataset name.

#### Adding a dataset to a plugin

New datasets can be added to the plugin, as long as the corresponding class is created:

```
- ["dataset-plugin-rain-observations=climetlab_dataset_plugin.rain_observations:
  ↵RainObservations"]
+ ["dataset-plugin-rain-observations=climetlab_dataset_plugin.rain_observations:
  ↵RainObservations",
+   "dataset-plugin-rain-forecast     =climetlab_dataset_plugin.rain_observations:
  ↵RainForecast"]
```

## CliMetLab hooks

---

**Todo:** Document .source attribute, to\_xarray(), to\_pandas(), to\_etc() Point to decorator

---

## 1.19 How to create a dataset plugin (YAML)

YAML file definitions can be used for simple datasets which rely on existing built-in *data source*, and cannot be as flexible to end-users. The following example shows how to use a source when the data consists of a single file downloadable from a URL.

```
---
```

```
dataset:
    source: url
    args:
        url: http://get.ecmwf.int/test-data/metview/gallery/temp.bufr

    metadata:
        documentation: Sample BUFR file containing TEMP messages
```

---

### Todo:

Document the YAML file way to create a dataset. Choose a good way to implement the workflow.

- Create a dataset YAML file.
  - Distribute it.
- 

## 1.20 How to create a source plugin

A *Data source* is a Python class that accesses data from a given location. CliMetLab has build-in sources (the most common being the “url” source) and a plugin can add more sources capabilities. A Source provides access to data, the code performing the actual reading can either be located in the Source itself or delegated to a Reader class. .. See details in Source class.

---

**Note: Naming convention:** A plugin package name should preferably starts with `climetlab-` and use “`-`”. The Python package to import should starts with `climetlab_` and use “`_`”.

---

### 1.20.1 Adding a new source as a pip plugin

The plugin mechanism for data sources relies on `entry_points`. In the `setup.py` file of the package, we should have the `entry_points` integration as follow:

```
setuptools.setup(
    entry_points={"climetlab.sources": [
        "source-name = package_name:ClassName"
    ]}
)
```

The package name and the class name should match the class defined in the code of the plugin:

- **source-name**: is the string that will be used in `cml.load_source("source-name", ...)` in order to trigger the source plugin code.
- **package\_name**: is the python package, as it would be used in `import package_name`
- **ClassName**: is the source class which inherits from `climetlab.Source`, it must be importable from the package\_name as `from package_name import ClassName`.

### 1.20.2 Example

As an example, the code located at <https://github.com/ecmwf/climetlab-demo-source> creates build a pip package named `climetlab-demo-source`.

This data source plugin allows accessing data from a SQL database using CliMetLab.

Once the plugin is installed (with `pip`), tabular data can be read from as follow:

```
>>> import climetlab as cml
>>> s = cml.load_source(
    "climetlab-demo-source",
    "sqlite:///test.db",
    "select * from data;",
    parse_dates=["time"],
)
df = s.to_pandas()
```

The integration is performed by `entry_points` called from `setup.py`.

```
setuptools.setup(
    entry_points={"climetlab.sources": [
        "demo-source = climetlab_demo_source:DemoSource"
    ]}
)
```

## 1.21 Normalize decorator

This section discusses *the purpose* of the `@normalize` decorator, shows *how to use it* and provides the *reference documentation*.

### 1.21.1 Purpose (discussion)

When sharing code, a large amount of code is usually dedicated to processing the arguments of the functions or methods to check their value and normalize it to a standard format.

The Python language offers the ability to accept a large range of input type on a unique function through *duck typing*. This leads to better integration of the different objects at stake, for instance using an object such as `xarray.Dataset` or a `pandas.DataFrame` or `pandas.Series` as input to provide a list of dates.

CliMetLab offers predefined shortcuts to implement this. The short API aims to address 80% of the use cases using the `@normalize` decorator. The longer form aims to tackle specific needs.

Compare the following codes snippets:

Boilerplate code

Tedious and error-prone Python code is needed to check and normalize the values of the function arguments given by the user.

```
def __init__(self, date, option):
    if date is None:
        date = DEFAULT_DATE_LIST
    if isinstance(date, tuple):
        date = list(date)
    if not isinstance(date, list):
        date = [date]
    for d in date:
        check_date_is_sunday(d)
    if not option in VALID_OPTIONS:
        raise ValueError(f"option={option} invalid")
    ...
    (more checks and transformations)
    ...
    do_stuff(date, option)
```

Using CliMetLab short form API

The decorator `@normalize` provides generic default behaviour to handle domain-specific arguments (for dates, meteorological and climate parameters, bounding boxes, etc.)

```
from climetlab.decorators import normalize
@normalize("date", "date(%Y%m%d)")
@normalize("option", ["foo", "bar"])
def __init__(self, date, option):
    do_stuff(date, option)
```

### 1.21.2 How to use

- How to ensure that the value in the function belongs to a list?

```
from climetlab.decorators import normalize

@normalize("param", ["tp", "gh"])
def f(self, param):
    print(param)
```

- How to ensure that the value in the function is a date with this format “YYYY-MM-DD”?

```
from climetlab.decorators import normalize

@normalize("option", "date(%Y-%m-%d)")
def f(option):
    return option

assert f(option="2022-12-31") == "2022-12-31"
assert f(option="20221231") == "2022-12-31"
assert f(option=20221231) == "2022-12-31"
```

- How to ensure that the value in the function is a list?

Add the keyword argument `multiple=True`. Not available for bounding-box.

- How to ensure that the value in the function is a list of int?

```
from climetlab.decorators import normalize

@normalize("option", "int", multiple=True)
def f(option):
    return option

# Alternative shorter version
@normalize("option", "int-list")
def g(option):
    return option

assert f(option="2022") == [2022]
assert g(option="2022") == [2022]
assert f(option=[48, 72.0, "96"]) == [48, 72, 96]
assert g(option=[48, 72.0, "96"]) == [48, 72, 96]
```

- How to ensure that the value in the function is not a list?

Add the keyword argument `multiple=False`.

- How to accept list or non-list as input?

Add the keyword argument `multiple=None`. Not available for bounding-box.

- How to add alias/shortcuts/special values to be replaced by actual predefined values?

Use the keyword argument `alias` and provide a dictionary.

```
from climetlab.decorators import normalize

@normalize("param", ["tp", "gh"])
def f(param):
    return param

assert f(param="tp") == "tp"
# f(param="t2m") # fails
```

```
from climetlab.decorators import normalize

DATES = dict(
    april=["20210401", "20210402", "20210403"],
    june=["20210610", "20210611"],
)

@normalize("x", "date-list(%Y%m%d)", aliases=DATES)
def f(x):
    return x

assert f("2021-06-10") == ["20210610"]
assert f("june") == ["20210610", "20210611"]
assert f("1999-01-01") == ["19990101"]
```

### 1.21.3 Reference

**Warning:** This API is experimental, things may change.

`@normalize(name, values, aliases={}, multiple=None, **kwargs)`

The `@normalize` decorator transforms the arguments provided when calling the decorated function, modifies it if needed, and provides a normalised value to the function. It ensures that the value of the argument is what is expected to be processed by the function.

**values** If *values* is a list, the list provides allowed values for the parameter. If *values* is a string, it is expected to be a shortcut similar to “`type(options)`” where `type` is one of the following: “`date`”, “`date-list`”, “`bounding-box`”. These shorts cut aims at providing an easy way to define many options in a more concise manner.

Example: “`date-list(%Y%m%d)`”

**type** Type of value expected by the function. The type should be one of the following: “`str`”, “`int`”, “`float`”, “`date`”, “`date-list`”, “`str-list`”, “`int-list`”, “`float-list`”.

**format** The keyword argument *format* is available for `type = 'date'` and ‘`date-list`’. It provides the expected format according to `datetime.strftime`. Example: `format='%(Y%m%d)`’

**convention** Experimental. To be documented.

**aliases** Replace a value with another using a dictionary of aliases.

**multiple** The keyword argument *multiple* is not available for bounding-box.

*True*: Ensure a list value. Turn input into a list if needed.

*False*: Ensure a non-list value. Turn a list input as non-list if the list has only one element. Fails with ValueError if the list has more than one element.

*None*: Accept list and non-list values without transformations.

## 1.22 Availability decorator

---

**Todo:** Not implemented yet

---

### 1.22.1 Purpose

When sharing code, a large amount of code is usually dedicated to processing the arguments of the functions or methods where users are requesting data. This boilerplate code needs to check their values and ensure that data is actually available. In case of failure, it would be helpful to generate an appropriate error message to the user, in order to help them understand why the call to the function was not successful.

CliMetLab offers predefined shortcuts to implement this. The short API aims to address the most common use cases using the @availability decorator.

Example:

```
@availability("availability.json")
def func(date, option):
    do_stuff(date, option)
```

### 1.22.2 Usage

### 1.22.3 Reference

## 1.23 Alias argument decorator

This section discusses the purpose of the @alias\_argument decorator, shows how to use it and provides reference documentation.

### 1.23.1 Purpose

This decorator allows a function to accept a range of parameters names, to make the interface easier to use for the end-user.

```
from climetlab.decorators import alias_argument

@alias_argument(param="parameter")
def func(param, other):
    return "param=" + param

func(param="tp", other=1)
# -> param=tp

func(parameter="tp", other=1)
# -> param=tp
```

The decorator also accept a list of alias values.

```
from climetlab.decorators import alias_argument

@alias_argument(param=["parameter", "variable"])
def func(param, other=1):
    return "param=" + param

func(param="tp")
# -> param=tp

func(parameter="tp")
# -> param=tp

func(variable="tp")
# -> param=tp
```

## 1.24 GRIB support

CliMetLab provides built-in functionalities regarding GRIB format handling.

### 1.24.1 Reading GRIB files

- CliMetLab can read *gridded* GRIB files (or urls) and provide data as `xarray.Dataset` objects. This can be performed using `cml.load_source("file", "myfile.grib")`.
- In addition to reading GRIB from local or remote sources, CliMetLab can also use a precomputed index, avoiding the need to parse the GRIB file to know its content. Using this index allows partial read of local files, and merging of multiple GRIB sources.

This can be performed using `cml.load_source("indexed-directory", "my/dir")`. To allow fast access to the data in the directory, CliMetLab relies on an index. Note that the index must have been created on this directory, CliMetLab will create one (see GRIB indexing below).

### 1.24.2 Writing GRIB files

There are two ways to write GRIB files:

- To save data from MARS, CDS or other, when GRIB is already the native format of the data, use the `source.save(filename)` method. This method is implemented only on a sources relying on GRIB.
- CliMetLab also supports writing custom GRIB files, with **modified values or custom attributes** through the function ``cml.new_grib_output()`. See usage example in the example notebook ([Examples](#)).

### 1.24.3 Building indexes

CliMetLab can create GRIB index files through its command line interface.

#### How to build a index for a directory containing GRIB files ?

```
climetlab index_directory my/dir
```

This will create a CliMetLab index file in `my/local/dir`, allowing other to access the data with `cml.load_source("indexed-directory", "my/dir")`.

#### How to build a index for one given URL containing a GRIB file ?

```
climetlab index_url "https://get.ecmwf.int/repository/test-data/climetlab/test-data/
˓→input/indexed-urls/large_grib_1.grb" > large_grib_1.index
```

Then upload the file `large_grib_1.index` and make sure it is available at: "[https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/indexed-urls/large\\_grib\\_1.index](https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/indexed-urls/large_grib_1.index)"

This allows accessing the data with

```
cml.load_source("indexed-url",
                 "https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/
˓→indexed-urls/large_grib_1.grb"
               )
```

### How to build indexes for a set of URLs containing GRIB files ?

Or, if you do the same for another URL “[https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/indexed-urls/large\\_grib\\_2.grb](https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/indexed-urls/large_grib_2.grb)”.

```
climetlab index_url "https://get.ecmwf.int/repository/test-data/climetlab/test-data/
˓→input/indexed-urls/large_grib_1.grb" > large_grib_1.index
climetlab index_url "https://get.ecmwf.int/repository/test-data/climetlab/test-data/
˓→input/indexed-urls/large_grib_2.grb" > large_grib_2.index
```

Then upload the files *large\_grib\_1.index* and *large\_grib\_2.index* and make sure they are available on the server at: “[https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/indexed-urls/large\\_grib\\_1.index](https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/indexed-urls/large_grib_1.index)” “[https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/indexed-urls/large\\_grib\\_2.index](https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/indexed-urls/large_grib_2.index)”

This allows accessing the data with

```
cml.load_source("indexed-urls",
                 "https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/
˓→indexed-urls/large_grib_{n}.grb",
                 {"n": [1, 2]},  
)
```

### How to build a index for a set of URLs containing GRIB files ?

---

**Todo:** Not implemented yet.

---

```
climetlab index_urls --base-url "https://get.ecmwf.int/repository/test-data/climetlab/
˓→test-data/input/indexed-urls" large_grib_1.grb large_grib_2.grb > global_index.index
```

Then upload the file *global\_index.index* and make sure it is available at: “[https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/indexed-urls/global\\_index.index](https://get.ecmwf.int/repository/test-data/climetlab/test-data/input/indexed-urls/global_index.index)”

This allows others to access the data with :

### 1.24.4 How to export files from the CliMetLab cache to another directory ?

When using CliMetLab to access MARS, CDS or other source, data is cached into the CliMetLab cache directory (the cache folder is `climetlab settings cache-directory`).

To prevent the cache from growing forever, old data in the cache directory are deleted automatically by CliMetLab when new data is downloaded. CliMetLab can create a shareable directory with some of the data from the cache through its command line interface.

```
climetlab export_cache DIRECTORY --help
```

---

**Todo:** Update this when mirror implementation changes.

---

**Warning:** This part of CliMetLab is still a work in progress. Documentation and code behaviour will change.

## 1.25 Plotting

---

**Todo:** Explain how to contribute layers, projections and styles

---

### CliMetLab Developer Guide

- *Overview*
- *Help wanted*
- *Architecture*
- *Plotting*
- *Gallery*
- *Climetlab Plugin mechanism*

## 1.26 Overview

The is the **CliMetLab** developer guide part of the CliMetLab documentation.

The CliMetLab documentation is split as follow:

- ***Getting started:*** General introduction with the main idea described there.
- ***User guide:*** This is the part you should read if you are using CliMetLab and plugins developed by others.
- ***Plugin Developer guide:*** describes how to create plugins (or YAML files) to add data and functionalities to CliMetLab, to make it available to the users above. In order to avoid rewriting the same code over and over, consider distributing it, the design of CliMetLab allows to do this with plugins.
- ***CliMetLab Developers guide:*** Please refer to this part either if you are willing to develop further CliMetLab or if you want to achieve something that is not possible with the current plugin framework.

## 1.27 Help wanted

CliMetLab is still experimental and its development status is still Alpha. Here are the parts that would need work and/or benefit from a community contribution.

Backward compatibility is not ensured as long a version 1.0 is not released. Nevertheless the functionalities are expected to be usable and stable, please submit a issue if needed (pull request welcome).

### 1.27.1 How can I to contribute ?

- Submit bug reports, propose enhancements, on github.
- You can also contribute to the core code by forking and submitting a pull request.
- TODO: fill this todo list.

## 1.28 Architecture

Message dispatch

With:

## 1.29 Plotting

### 1.29.1 mcoast

This action controls the plotting of coastlines, rivers, cities and country boundaries, as well as the latitude/longitude grid lines.

Name	Type	Default
<b>map_coastline_general_style</b> Use a predefined style depending on the general theme	str	""
<b>map_coastline</b> Plot coastlines on map (ON/OFF)	bool	True
<b>map_grid</b> Plot grid lines on map (On/OFF)	bool	True
<b>map_label</b> Plot label on map grid lines (On/OFF)	bool	True
<b>map_coastline_resolution</b> Select one of the pre-defined resolutions: automatic, low, medium, and high. When set to AUTOMATIC, a resolution appropriate to the scale of the map is chosen in order to balance quality with speed.	“automatic”, “low”, “medium”, “high”	“automatic”
<b>map_coastline_land_shade</b> Sets if land areas are shaded	bool	False
<b>map_coastline_land_shade_colour</b> Colour of Shading of land areas	str	“green”

continues on next page

Table 1 – continued from previous page

Name	Type	Default
<b>map_coastline_sea_shade</b> Shade the sea areas	bool	False
<b>map_coastline_sea_shade_colour</b> Colour of Shading of sea areas	str	“blue”
<b>map_boundaries</b> Add the political boundaries	bool	False
<b>map_cities</b> Add the cities (capitals)	bool	False
<b>map_rivers</b> Display rivers (on/off)	bool	False
<b>map_rivers_style</b> Line style for rivers	“solid”, “dash”, “dot”, “chain_dash”, “chain_dot”	“solid”
<b>map_rivers_colour</b> Colour of the rivers	str	“blue”
<b>map_rivers_thickness</b> Line thickness of rivers	int	1
<b>map_user_layer</b> Display user shape file layer	bool	False
<b>map_user_layer_name</b> Path + name of the shape file to use	str	“”
<b>map_user_layer_projection</b> Projection used in the shape file	str	“”

continues on next page

Table 1 – continued from previous page

Name	Type	Default
<b>map_user_layer_style</b> Line style for User Layer	“solid”, “dash”, “dot”, “chain_dash”, “chain_dot”	“solid”
<b>map_user_layer_colour</b> Colour of the User Layer	str	“blue”
<b>map_user_layer_thickness</b> Line thickness of User Layer	int	1
<b>map_coastline_colour</b> Colour of coastlines	str	“black”
<b>map_coastline_style</b> Line style of coastlines	“solid”, “dash”, “dot”, “chain_dash”, “chain_dot”	“solid”
<b>map_coastline_thickness</b> Line thickness of coastlines	int	1
<b>map_grid_latitude_reference</b> Reference Latitude from which all latitude lines are drawn	float	0.0
<b>map_grid_latitude_increment</b> Interval between latitude grid lines	float	10.0
<b>map_grid_longitude_reference</b> Reference Longitude from which all longitude lines are drawn	float	0.0
<b>map_grid_longitude_increment</b> Interval between longitude grid lines	float	20.0

continues on next page

Table 1 – continued from previous page

Name	Type	Default
<b>map_grid_line_style</b> Line style of map grid lines	“solid”, “dash”, “dot”, “chain_dash”, “chain_dot”	“solid”
<b>map_grid_thickness</b> Thickness of map grid lines	int	1
<b>map_grid_colour</b> Colour of map grid lines	str	“black”
<b>map_grid_frame</b> Add a frame around the projection	bool	False
<b>map_grid_frame_line_style</b> Line style of map grid lines	“solid”, “dash”, “dot”, “chain_dash”, “chain_dot”	“solid”
<b>map_grid_frame_thickness</b> Thickness of map grid lines	int	1
<b>map_grid_frame_colour</b> Colour of map grid lines	str	“black”
<b>map_label_font</b> Font of grid labels	str	“sansserif”
<b>map_label_font_style</b> Font of grid labels	str	“normal”
<b>map_label_colour</b> Colour of map labels	str	“black”

continues on next page

Table 1 – continued from previous page

Name	Type	Default
<b>map_label_height</b> Height og grid labels	float	0.25
<b>map_label_blanking</b> Blanking of the grid labels	bool	True
<b>map_label_latitude_frequency</b> Evry Nth latitue grid is labelled	float	1.0
<b>map_label_longitude_frequency</b> Evry Nth longitude grid is labelled	float	1.0
<b>map_label_left</b> Enable the labels on the left of the map	bool	True
<b>map_label_right</b> Enable the labels on the right of the map	bool	True
<b>map_label_top</b> Enable the labels on the top of the map	bool	True
<b>map_label_bottom</b> Enable the labels on the bottom of the map	bool	True

## 1.29.2 mcont

This action controls the plotting of isolines, contour bands and grid points. It is used to plot gridded data, such as fields.

Name	Type	Default
<b>legend</b> Turn legend on or off	bool	False

continues on next page

Table 2 – continued from previous page

Name	Type	Default
<b>contour</b> Turn contouring on or off	bool	True
<b>contour_method</b> Contouring method	“automatic”, “linear”, “akima760”, “akima474”	“automatic”
<b>contour_interpolation_floor</b> Any value below this floor will be forced to the floor value. avoid the bubbles artificially created by the interpolation method	float	-2147483647.0
<b>contour_interpolation_ceiling</b> any value above this ceiling will be forced to the ceiling value. avoid the bubbles artificially created by the interpolation method	float	2147483647.0
<b>contour_automatic_setting</b> Turn the automatic setting of contouring attributes	False, “style_name”, “ecmwf”	False
<b>contour_style_name</b> Use of a predeined setting	str	“”
<b>contour_metadata_only</b> Only get the metadata	bool	False
<b>contour_hilo</b> Plot local maxima/minima	1, 0, “hi”, “lo”	False
<b>contour_grid_value_plot</b> Plot Grid point values	bool	False
<b>contour_akima_x_resolution</b> X resolution of Akima interpolation.	float	1.5

continues on next page

Table 2 – continued from previous page

Name	Type	Default
<b>contour_akima_y_resolution</b> Y resolution of Akima interpolation.	float	1.5
<b>contour_grid_value_min</b> The minimum value for which grid point values are to be plotted	float	-1e+21
<b>contour_grid_value_max</b> The maximum value for which grid point values are to be plotted	float	1e+21
<b>contour_grid_value_lat_frequency</b> The grid point values in every Nth latitude row are plotted	int	1
<b>contour_grid_value_lon_frequency</b> The grid point values in every Nth longitude column are plotted	int	1
<b>contour_grid_value_height</b> Height of grid point values	float	0.25
<b>contour_grid_value_colour</b> Colour of grid point values	str	“blue”
<b>contour_grid_value_format</b> Format of grid point values	str	“(automatic)”
<b>contour_grid_value_marker_height</b> Height of grid point markers	float	0.25
<b>contour_grid_value_marker_colour</b> Colour of grid point markers	str	“red”
<b>contour_grid_value_marker_qual</b> Quality of the grid point marker	“high”, “medium”, “low”	“low”

continues on next page

Table 2 – continued from previous page

Name	Type	Default
<b>contour_grid_value_marker_index</b> Table number of marker index. See Appendix for Plotting Attributes	int	3
<b>contour_grid_value_position</b> Position of the value	“right”, “left”, “bottom”, “top”	“top”
<b>contour_shade_max_level_colour</b> Highest shading band colour	str	“blue”
<b>contour_shade_min_level_colour</b> Lowest shading band colour	str	“red”
<b>contour_shade_colour_direction</b> Direction of colour sequencing for shading	“clockwise”, “anti_clockwise”	“anti_clockwise”
<b>contour_shade_cell_resolution</b> Number of cells per cm for CELL shading	float	10.0
<b>contour_shade_cell_method</b> NMETHOD of determining the colour of a cell	“nearest”, “interpolate”	“nearest”
<b>contour_shade_cell_resolution_method</b> if adaptive, magics will switch to grid_shading when the data resolution is greater than the requested resolution	“classic”, “adaptive”	“classic”
<b>contour_max_level</b> Highest level for contours to be drawn	float	1e+21
<b>contour_min_level</b> Lowest level for contours to be drawn	float	-1e+21
<b>contour_shade_max_level</b> Highest level for contours to be shaded	float	1e+21

continues on next page

Table 2 – continued from previous page

Name	Type	Default
<b>contour_shade_min_level</b> Lowest level for contours to be shaded	float	-1e+21
<b>contour_level_count</b> Count or number of levels to be plotted. Magics will try to find “nice levels”, this means that the number of levels could be slightly different from the asked number of levels	int	10
<b>contour_level_tolerance</b> Tolerance: Do not use nice levels if the number of levels is really to different [count +/- tolerance]	int	2
<b>contour_reference_level</b> Contour level from which contour interval is calculated	float	0.0
<b>contour_shade_dot_size</b> Size of dot in shading pattern	float	0.02
<b>contour_shade_max_level_density</b> Dots/square centimetre in highest shading band	float	50.0
<b>contour_shade_min_level_density</b> Dots/square centimetre in lowest shading band	float	1.0
<b>contour_gradients_colour_list</b> Colour used at the stops : the gradeint will be calculated between 2 consecutive ones.	List[str]	[]
<b>contour_gradients_waypoint_method</b> waypoints at the left, right, middle of the interval.	“both”, “ignore”, “left”, “right”	“both”
<b>contour_gradients_technique</b> Technique to apply to compute the gradients rgb/hcl/hsl	“rgb”, “hcl”, “hsl”	“rgb”

continues on next page

Table 2 – continued from previous page

Name	Type	Default
<b>contour_gradients_technique_direction</b> Technique to apply to compute the gradients clockwise/anticlockwise	“clockwise”, “anti_clockwise”, “shortest”, “longest”	“clockwise”
<b>contour_gradients_step_list</b> Number of steps to compute for each interval	List[int]	[]
<b>contour_shade_method</b> Method used for shading	“area_fill”, “solid”, “dot”, “hatch”	“dot”
<b>contour_grid_shading_position</b> Middle : the point is in the middle of the cell, bottom_left : the point is in the bottom left corner	“middle”, “bottom_left”	“middle”
<b>contour_shade_hatch_index</b> The hatching pattern(s) to use. 0 Provides an automatic sequence of patterns, other values set a constant pattern across all contour bands.	int	0
<b>contour_shade_hatch_thickness</b> Thickness of hatch lines	int	1
<b>contour_shade_hatch_density</b> Number of hatch lines per cm.	float	18.0
<b>contour_hilo_height</b> Height of local maxima/minima text or numbers	float	0.4
<b>contour_hi_colour</b> Colour of local maxima text or number	str	“blue”
<b>contour_lo_colour</b> Colour of local minima text or number	str	“blue”

continues on next page

Table 2 – continued from previous page

Name	Type	Default
<b>contour_hilo_format</b> Format of HILO numbers (MAGICS Format/(AUTOMATIC))	str	“(automatic)”
<b>contour_hilo_marker_height</b> Height of HighLow marker symbol	float	0.1
<b>contour_hilo_marker_index</b> Index of marker symbol	int	3
<b>contour_hilo_marker_colour</b> Colour of grid point markers	str	“red”
<b>contour_hi_text</b> Text to represent local maxima	str	“H”
<b>contour_lo_text</b> Text to represent local minima	str	“L”
<b>contour_hilo_blanking</b> Blank around highs and lows	bool	False
<b>contour_hilo_type</b> Type of high/low (TEXT/NUMBER/BOTH)	“text”, “number”, “both”	“text”
<b>contour_hilo_window_size</b> Size of the window used to calculate the Hi/Lo	int	3
<b>contour_hilo_max_value</b> Local HiLo above specified value are not drawn	float	1e+21
<b>contour_hilo_min_value</b> Local HiLo below specified value are not drawn	float	-1e+21

continues on next page

Table 2 – continued from previous page

Name	Type	Default
<b>contour_hi_max_value</b> Local HI above specified value are not drawn	float	1e+21
<b>contour_hi_min_value</b> Local HI below specified value are not drawn	float	-1e+21
<b>contour_lo_max_value</b> Local Lo above specified value are not drawn	float	1e+21
<b>contour_lo_min_value</b> Local Lo below specified value are not drawn	float	-1e+21
<b>contour_hilo_marker</b> Plot hilo marker (ON/OFF)	bool	False
<b>contour_interval</b> Interval in data units between two contour lines	float	8.0
<b>contour_highlight_style</b> Style of highlighting (SOLID/ DASH/ DOT/ CHAIN_DASH/ CHAIN_DOT)	“solid”, “dash”, “dot”, “chain_dash”, “chain_dot”	“solid”
<b>contour_highlight_colour</b> Colour of highlight line	str	“blue”
<b>contour_highlight_thickness</b> Thickness of highlight line	int	3
<b>contour_highlight_frequency</b> Frequency of highlight line	int	4
<b>contour_label_type</b> Type of label (text/number/both)	“text”, “number”, “both”	“number”

continues on next page

Table 2 – continued from previous page

Name	Type	Default
<b>contour_label_text</b> Text for labels	str	“”
<b>contour_label_height</b> Height of contour labels	float	0.3
<b>contour_label_format</b> Format of contour labels (MAGICS Format/(AUTOMATIC))	str	“(automatic)”
<b>contour_label_blanking</b> Label Blanking	bool	True
<b>contour_label_font</b> Name of the font	str	“sansserif”
<b>contour_label_font_style</b> Style of the font normal/bold/italic	“normal”, “bold”, “italic”	“normal”
<b>contour_label_colour</b> Colour of contour labels	str	“contour_line_colour”
<b>contour_label_frequency</b> Every Nth contour line is labelled	int	2
<b>contour_shade_technique</b> Technique used for shading (POLYGON_SHADING/ CELL_SHADING/ MARKER)	“polygon_shading”, “grid_shading”, “cell_shading”, “dump_shading”, “marker”	“polygon_shading”
<b>contour_shade_colour_method</b> Method of generating the colours of the bands in contour shading (list/calculate/advanced)	“calculate”, “list”, “gradients”, “palette”	“calculate”

continues on next page

Table 2 – continued from previous page

Name	Type	Default
<b>contour_level_list</b> List of contour levels to be plotted	List[float]	[]
<b>contour_shade_colour_list</b> List of colours to be used in contour shading.	List[str]	[]
<b>contour_shade_colour_table</b> Colour table to be used with marker shading technique	List[str]	[]
<b>contour_shade_height_table</b> Height table to be used with marker shading technique	List[float]	[]
<b>contour_shade_marker_table_type</b> index: using contour_shade_marker_table and defining the markers by index, name: using contour_shade_marker_name_table and defining the symbols by their names	“index”, “name”	“index”
<b>contour_shade_marker_table</b> Marker table to be used with marker shading technique	List[int]	[]
<b>contour_shade_marker_name_table</b> Marker name table to be used with marker shading technique	List[str]	[]
<b>contour_line_style</b> Style of contour line	“solid”, “dash”, “dot”, “chain_dash”, “chain_dot”	“solid”
<b>contour_line_thickness</b> Thickness of contour line	int	1
<b>contour_line_colour_rainbow</b> if On, rainbow colouring method will be used.	bool	False

continues on next page

Table 2 – continued from previous page

Name	Type	Default
<b>contour_line_colour</b> Colour of contour line	str	“blue”
<b>contour_line_colour_rainbow_method</b> Method of generating the colours for isoline	“calculate”, “list”	“calculate”
<b>contour_line_colour_rainbow_max_level_colour</b> Colour to be used for the max level	str	“blue”
<b>contour_line_colour_rainbow_min_level_colour</b> Colour to be used for the mainlevel	str	“red”
<b>contour_line_colour_rainbow_direction</b> Direction of colour sequencing for colouring	“clockwise”, “anti_clockwise”	“anti_clockwise”
<b>contour_line_colour_rainbow_colour_list</b> List of colours to be used in rainbow isolines	List[str]	[]
<b>contour_line_colour_rainbow_colour_list_policy</b> What to do if the list of colours is smaller than the list of contour: lastone/cycle	“lastone”, “cycle”	“lastone”
<b>contour_line_thickness_rainbow_list</b> List of thickness to used when rainbow method is on	List[int]	[]
<b>contour_line_thickness_rainbow_list_policy</b> What to do if the list of thickness is smaller than the list of contour: lastone/cycle	“lastone”, “cycle”	“lastone”
<b>contour_line_style_rainbow_list</b> List of line style to used when rainbow method is on	List[str]	[]
<b>contour_line_style_rainbow_list_policy</b> What to do if the list of line styles is smaller than the list of contour: lastone/cycle	“lastone”, “cycle”	“lastone”

continues on next page

Table 2 – continued from previous page

Name	Type	Default
<b>contour_highlight</b> Plot contour highlights (ON/OFF)	bool	True
<b>contour_level_selection_type</b> count: calculate a reasonable contour interval taking into account the min/max and the requested number of isolines. interval: regularly spaced intervals using the reference_level as base. level_list: uses the given list of levels.	“count”, “interval”, “level_list”	“count”
<b>contour_label</b> Plot labels on contour lines	bool	True
<b>contour_shade</b> Turn shading on	bool	False
<b>contour_legend_only</b> Inform the contour object do generate only the legend and not the plot!	bool	False
<b>contour_shade_palette_name</b> Colour used at the stops : the gradient will be calculated between 2 consecutive ones.	str	“”
<b>contour_shade_palette_policy</b> What to do if the list of colours is smaller than the list of levels: lastone/cycle	“lastone”, “cycle”	“lastone”
<b>contour_grid_value_type</b> For Gaussian fields, plot normal (regular) values or reduced grid values. (NORMAL/REDUCED/akima). If akima, the akima grid values will be plotted	“normal”, “reduced”, “akima”	“normal”
<b>contour_grid_value_plot_type</b> (VALUE/MARKER/BOTH)	“value”, “marker”, “both”	“value”

### 1.29.3 mmap

Name	Type	Default
<b>subpage_x_axis_type</b>	“regular”, “date”, “geoline”, “logarithmic”	“regular”
<b>subpage_y_axis_type</b>	“regular”, “date”, “geoline”, “logarithmic”	“regular”
<b>x_min</b>	float	0.0
<b>subpage_x_automatic</b>	bool	False
<b>subpage_y_automatic</b>	bool	False
<b>x_max</b>	float	100.0
<b>y_min</b>	float	0.0
<b>y_max</b>	float	100.0
<b>thermo_annotation_width</b> Percentage of the width used to display the annotation on the right side .	float	25.0
<b>subpage_x_position</b> Y-Coordinate of lower left hand corner of subpage in cm. -1 is the default: 7.5% of the parent page	float	-1.0

continues on next page

Table 3 – continued from previous page

Name	Type	Default
<b>subpage_y_position</b> X-Coordinate of lower left hand corner of subpage in cm. -1 is the default: 5% of the parent page	float	-1.0
<b>subpage_x_length</b> Length of subpage in horizontal direction in cm. -1 is the default: 85% of the parent page	float	-1.0
<b>subpage_y_length</b> Length of subpage in vertical direction in cm. -1 is the default: 85% of the parent page	float	-1.0
<b>subpage_map_library_area</b> if On, pickup a predefined geographical area	bool	False
<b>subpage_map_area_name</b> Name of the predefined area	str	False

continues on next page

Table 3 – continued from previous page

Name	Type	Default
<b>subpage_map_projection</b> Projection to set in the drawing area	“cylindrical”, “polar_stereographic”, “polar_north”, “polar_south”, “geos”, “meteosat”, “meteosat_57E”, “goes_east”, “lambert”, “EPSG:3857”, “EPSG:900913”, “EPSG:32661”, “EPSG:32761”, “EPSG:4326”, “goode”, “collignon”, “mollweide”, “robinson”, “bonne”, “google”, “efas”, “tpers”, “automatic”, “lambert_north_atlantic”, “mercator”, “cartesian”, “taylor”, “tephigram”, “skewt”, “emagram”	“cylindrical”
<b>subpage_clipping</b> Apply a clipping to the subpage to avoid any symbol, flag or arrow to go outside of the plotting area	bool	False
<b>subpage_background_colour</b> Colour of the subpage background	str	“none”
<b>subpage_frame</b> Plot frame around subpage (ON/OFF)	bool	True
<b>subpage_frame_colour</b> Colour of subpage frame (Full choice of colours)	str	“charcoal”

continues on next page

Table 3 – continued from previous page

Name	Type	Default
<b>subpage_frame_line_style</b> Style of subpage frame (SOLID/DASH/DOT/CHAIN_DASH/CHAIN_DOT)	“solid”, “dash”, “dot”, “chain_dash”, “chain_dot”	“solid”
<b>subpage_frame_thickness</b> Thickness of subpage frame	int	2
<b>subpage_vertical_axis_width</b> width of the vertical axis in cm	float	1.0
<b>subpage_horizontal_axis_height</b> height of the horizontal axis in cm	float	0.5
<b>subpage_align_horizontal</b> Used in automatic layout to setup the horizontal alignment of the drawing area in the subpage	“left”, “right”	“left”
<b>subpage_align_vertical</b> Used in automatic layout to setup the vertical alignment of the drawing area in the subpage	“bottom”, “top”	“bottom”
<b>subpage_lower_left_latitude</b> Latitude of lower left corner of map.	float	-90.0
<b>subpage_lower_left_longitude</b> Longitude of lower left corner of map	float	-180.0
<b>subpage_upper_right_latitude</b> Latitude of upper right corner of map	float	90.0
<b>subpage_upper_right_longitude</b> Longitude of upper right corner of map	float	180.0

continues on next page

Table 3 – continued from previous page

Name	Type	Default
<b>subpage_map_area_definition_polar</b> Method of defining a polar stereographic map	“full”, “corners”, “centre”	“corners”
<b>subpage_map_hemisphere</b> Hemisphere required for polar stereographic map(NORTH/SOUTH)	str	“north”
<b>subpage_map_vertical_longitude</b> Vertical longitude of polar stereographic or Aitoff map	float	0.0
<b>subpage_map_centre_latitude</b> Latitude of centre of polar stereographic map defined by ‘CENTRE’ or centre latitude of Lambert/satellite subarea projections	float	90.0
<b>subpage_map_centre_longitude</b> Longitude of centre of polar stereographic map defined by ‘CENTRE’ or centre longitude of Lambert/satellite subarea projections	float	0.0
<b>subpage_map_scale</b> Scale of polar stereographic or Aitoff map	float	50000000.0
<b>subpage_map_area_definition</b> method used to define the geographical area.	“corners”, “full”	“full”
<b>subpage_map_true_scale_north</b> Developement in progress	float	6.0
<b>subpage_map_true_scale_south</b> Developement in progress	float	-60.0
<b>subpage_map_projection_height</b> height (in meters) above the surface	float	42164000.0
<b>subpage_map_projection_tilt</b> angle (in degrees) away from nadir	float	0.0

continues on next page

Table 3 – continued from previous page

Name	Type	Default
<b>subpage_map_projection_azimuth</b> bearing (in degrees) from due north	float	20.0
<b>subpage_map_projection_view_latitude</b> latitude (in degrees) of the view position	float	20.0
<b>subpage_map_projection_view_longitude</b> longitude (in degrees) of the view position	float	-60.0
<b>subpage_map_geos_sweep</b> the sweep angle axis of the viewing instrument	float	0.0
<b>taylor_standard_deviation_min</b> Min of the Standard deviation axis.	float	0.0
<b>taylor_standard_deviation_max</b> Max of the Standard deviation axis.	float	1.0

#### 1.29.4 msymb

This action controls the plotting of meteorological and marker symbols. It is used to plot point data, such as observations.

Name	Type	Default
<b>symbol_advanced_table_selection_type</b> Technique to use to calculate the shading band levels.	“count”, “interval”, “list”	“count”
<b>symbol_advanced_table_min_value</b> Min value to plot	float	-1e+21
<b>symbol_advanced_table_max_value</b> Max value to plot	float	1e+21

continues on next page

Table 4 – continued from previous page

Name	Type	Default
<b>symbol_advanced_table_level_count</b> Count or number of levels to be plotted. Magics will try to find “nice levels”, this means that the number of levels could be slightly different from the requested number of levels	int	10
<b>symbol_advanced_table_level_tolerance</b> Tolerance: Do not use “nice levels” if the number of levels is really too different [count +/- tolerance]	int	2
<b>symbol_advanced_table_interval</b> Interval in data units between different bands of shading	float	8.0
<b>symbol_advanced_table_reference_level</b> Level from which the level interval is calculated	float	0.0
<b>symbol_advanced_table_level_list</b> List of shading band levels to be plotted	List[float]	[]
<b>symbol_advanced_table_colour_method</b> Method of generating the colours of the bands in polygon shading	“calculate”, “list”	“calculate”
<b>symbol_advanced_table_max_level_colour</b> Highest shading band colour	str	“blue”
<b>symbol_advanced_table_min_level_colour</b> Lowest shading band colour	str	“red”
<b>symbol_advanced_table_colour_direction</b> Direction of colour sequencing for plotting (CLOCKWISE/ ANTI_CLOCKWISE)	“clockwise”, “anti-clockwise”	“anti_clockwise”
<b>symbol_advanced_table_colour_list</b> List of colours to be used in symbol plotting	List[str]	[]

continues on next page

Table 4 – continued from previous page

Name	Type	Default
<b>symbol_advanced_table_colour_list_policy</b> What to do if the list of colours is smaller than the list of intervals: lastone/cycle	“lastone”, “cycle”	“lastone”
<b>symbol_advanced_table_marker_list</b> List of markers to be used in symbol plotting	List[int]	[]
<b>symbol_advanced_table_marker_name_list</b> List of markers to be used in symbol plotting symbol	List[str]	[]
<b>symbol_advanced_table_marker_list_policy</b> What to do if the list of markers is smaller than the list of intervals: lastone/cycle	“lastone”, “cycle”	“lastone”
<b>symbol_advanced_table_height_method</b> Method of generating the height	“calculate”, “list”	“list”
<b>symbol_advanced_table_height_max_value</b> Maximum height to use	float	0.2
<b>symbol_advanced_table_height_min_value</b> Mininimum height to use	float	0.1
<b>symbol_advanced_table_height_list</b> List of heights to be used	List[float]	[]
<b>symbol_advanced_table_height_list_policy</b> What to do if the list of heights is smaller than the list of intervals: lastone/cycle	“lastone”, “cycle”	“lastone”
<b>symbol_advanced_table_text_list</b> Text to display	List[str]	[]
<b>symbol_advanced_table_text_list_policy</b> What to do if the list of text is smaller that the list of intervals lastone: reuse the last one, cycle: return to the fisrt one	“lastone”, “cycle”	“cycle”

continues on next page

Table 4 – continued from previous page

Name	Type	Default
<b>symbol_advanced_table_text_font</b> Font to use for text plotting.	str	“sansserif”
<b>symbol_advanced_table_text_font_size</b> Font size	float	0.25
<b>symbol_advanced_table_text_font_style</b> Font Style	str	“normal”
<b>symbol_advanced_table_text_font_colour</b> Symbol Colour	str	“automatic”
<b>symbol_advanced_table_text_display_type</b> How to display text none:do not display it centre : display it instead of the symbol, right : attached it to the right of the symbol, top : attached it to the top of the symbol, bottom: attached it to the bottom of the symbol,	“centre”, “none”, “right”, “left”, “top”, “bottom”	“none”
<b>symbol_advanced_table_outlayer_method</b> outlayer method	“none”, “simple”	“none”
<b>legend_user_text</b> if set, the text to be shown for the symbol group in the legend	str	“”
<b>symbol_colour</b> Colour of symbols.	str	“blue”
<b>symbol_height</b> Height of symbols.	float	0.2
<b>symbol_marker_mode</b> Method to select a marker : by name, by index, by image : in that case, Magics will use an external image as marker.	str	“index”
<b>symbol_marker_index</b> Marker indice: An integer between 1 and 28	int	1

continues on next page

Table 4 – continued from previous page

Name	Type	Default
<b>symbol_marker_name</b> Symbol name. Choose in a list of available markers dot/circle/ww_00 ...	str	“dot”
<b>symbol_image_path</b> Path to the image	str	“”
<b>symbol_image_format</b> Format of the image file. If set to AUTOMATIC, the file extension will be used to determine the file type.	“automatic”, “png”, “svg”	“automatic”
<b>symbol_image_width</b> width of the image	float	-1.0
<b>symbol_image_height</b> height of the image	float	-1.0
<b>symbol_text_list</b> list of texts to plot	List[str]	[]
<b>symbol_text_position</b> Position of the text	“right”, “left”, “bottom”, “top”	“right”
<b>symbol_text_font</b> Font to use	str	“sansserif”
<b>symbol_text_font_size</b> Font size	float	0.25
<b>symbol_text_font_style</b> Font style	str	“normal”
<b>symbol_text_font_colour</b> Font colour.	str	“automatic”

continues on next page

Table 4 – continued from previous page

Name	Type	Default
<b>symbol_legend_height</b> If set, the height will be used to plot the symbols in the legend	float	-1.0
<b>legend</b> Turn legend on or off (ON/OFF) : New Parameter!	bool	False
<b>symbol_scaling_method</b> Turn legend on or off (ON/OFF) : New Parameter!	bool	False
<b>symbol_scaling_level_0_height</b> Turn legend on or off (ON/OFF) : New Parameter!	float	0.1
<b>symbol_scaling_factor</b> Turn legend on or off (ON/OFF) : New Parameter!	float	4.0
<b>symbol_type</b> Defines the type of symbol plotting required	“number”, “text”, “marker”, “wind”	“number”
<b>symbol_table_mode</b> Specifies if plotting is to be in advanced, table (on) or individual mode (off). Note: The simple table mode is not recommended anymore, try to use the advanced mode instead, this should give you easier control of the plot.	0, “advanced”, 1	“OFF”
<b>symbol_format</b> Format used to plot values (MAGICS Format/(AUTOMATIC))	str	“(automatic)”
<b>symbol_text_blanking</b> blanking of the text	bool	False
<b>symbol_outline</b> Add an outline to each symbol	bool	False
<b>symbol_outline_colour</b> Colour of the outline	str	“black”

continues on next page

Table 4 – continued from previous page

Name	Type	Default
<b>symbol_outline_thickness</b> thickness of the outline	int	1
<b>symbol_outline_style</b> Line Style of outline	“solid”, “dash”, “dot”, “chain_dash”, “chain_dot”	“solid”
<b>symbol_connect_line</b> Connect all the symbols with a line	bool	False
<b>symbol_connect_automatic_line_colour</b> if on, will use the colour of the symbol	bool	True
<b>symbol_connect_line_colour</b> Colour of the connecting line	str	“black”
<b>symbol_connect_line_thickness</b> thickness of the connecting line	int	1
<b>symbol_connect_line_style</b> Line Style of connecting line	“solid”, “dash”, “dot”, “chain_dash”, “chain_dot”	“solid”
<b>symbol_min_table</b> Table of minimum values. The table is used in conjunction with SYMBOL_MAX_TABLE	List[float]	[]
<b>symbol_max_table</b> Table of maximum values. The table is used in conjunction with SYMBOL_MIN_TABLE	List[float]	[]
<b>symbol_marker_table</b> Table of MARKER indices. The table is to be used in conjunction with SYMBOL_MIN_TABLE and SYMBOL_MAX_TABLE	List[int]	[]

continues on next page

Table 4 – continued from previous page

Name	Type	Default
<b>symbol_name_table</b> Table of Symbol names. The table is to be used in conjunction with SYMBOL_MIN_TABLE and SYMBOL_MAX_TABLE	List[str]	[]
<b>symbol_colour_table</b> Table of SYMBOL colours. T The table is to be used in conjunction with SYMBOL_MIN_TABLE and SYMBOL_MAX_TABLE	List[str]	[]
<b>symbol_height_table</b> Table of SYMBOL heights. The table is to be used in conjunction with SYMBOL_MIN_TABLE and SYMBOL_MAX_TABLE	List[float]	[]



### 1.29.5 mtable

Name	Type	Default
<b>table_filename</b> Path to the table data	str	""
<b>table_delimiter</b> Used delimiter	str	";"
<b>table_combine_delimiters</b> Consecutive delimiters will be considered as one	bool	False
<b>table_header_row</b> Which row (first is 1) is the header line on?	int	1
<b>table_data_row_offset</b> How many rows after the header row does the data start? 1 if no header row.	int	1
<b>table_meta_data_rows</b> List of row indexes containing meta-data of the form P1=V1 P2=V2.	List[int]	[]
<b>table_x_type</b> Type used for X variable_index: number or date	“number”, “date”	“number”
<b>table_y_type</b> Type used for Y variable_index: number or date	“number”, “date”	“number”
<b>table_variable_identifier_type</b> are we referring to the columns by names or index (index/name)	str	“index”
<b>table_x_variable</b> X variable_index or name	str	1
<b>table_y_variable</b> Y variable_index or name	str	Chapter 1. Documentation
		2

## 1.30 Gallery

### 1.30.1 Layers

default-background

default-foreground

land-sea

### 1.30.2 Styles

cyclone-track

default-style-fields

default-style-observations

land-sea-mask

no-style

orography

rainbow-markers

### 1.30.3 Projections

africa

**asia**

**bonne**

**collignon**

**euro-atlantic**

**europe**

**europe-cylindrical**

**global**

**goode**

**mercator**

**mollweide**

**north-america**

**north-america1**

**north-atlantic**

**north-hemisphere**

**polar-north**

**robinson**

**south-amERICA**

**south-atlantic**

**south-hemisphere**

**south-pacific**

**tropics-east**

**tropics-west**

**web-mercator**

## 1.31 Climetlab Plugin mechanism

This document discuss how plugins are integrated into CliMetLab. There are two ways to add a plugin into CliMetLab:

- A Python package using the standard [Python plugin](#) mechanism based on `entry_points`. This is the generic CliMetLab plugin mechanism.
- A YAML file can be also be used to create plugins, when the plugin is simple enough and used only generic predefined code. (currently only for [dataset plugins](#)).

### 1.31.1 Plugin as python packages using entry\_points

During the installation of the pip package, the plugin registers itself thanks to the entry points in its setup.py file, making CliMetLab aware of the new capabilities. Then, the user can take advantage of the shared code though the enhanced `climetlab.load_dataset()`, `climetlab.load_source()` and `climetlab.plot_map()`, etc.

For pip packages using `setuptools`, creating a plugin consists in adding an entry in `setup.py`:

```
setuptools.setup(
    name = 'climetlab-package-name',
    ...
    entry_points={"climetlab.<plugintype>":
        ["foo = climetlab_package_name:FooClass",
         "bar = climetlab_package_name:BarClass"]
    },
)
```

In this package called **climetlab-package-name**, the class `climetlab_package_name.FooClass` provides Python code related to "foo". Additional code related to "bar" is located in the class `climetlab_package_name.BarClass`. The `<plugintype>` is one of the plugin type in the table above: `dataset`, `sources`, readers, etc. See the individual documentation for each plugin type for detailed examples and the standard [`Python plugin documentation<https://packaging.python.org/guides/creating-and-discovering-plugins>`](https://packaging.python.org/guides/creating-and-discovering-plugins).

### 1.31.2 Plugin as YAML files

---

**Todo:** This is still a work-in-progress.

---

Additionally, for `dataset plugins` only, CliMetLab search for known locations to find a YAML file with a name matching the requested dataset. The YAML files are used to create an appropriate class.

---

**CHAPTER  
TWO**

---

**LICENSE**

*CliMetLab* is available under the open source Apache License.